

SUMMARY OF QUANTITIES

F.A.U. ROUTE	CONTRACT NO. 87330	COUNTY	TOTAL SHEET SHITS, NO.
5348	STATE SECTION 05-00160-00-WR	DEKALB	140 7
SUMMARY OF QUANTITIES			
F.H.W.A. REG.5 ILLINOIS PROJECT HPP-2295(001)			

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE							
				1000-2A ROADWAY	X028-2A BOX CULVERT	Y003 LANDSCAPING ORNAMENTAL	Y030-1E LIGHTING	Y030-1F SIGNALS S. MALTA RD./TAYLOR ST.	Y031-1F SIGNALS INTERCONNECT	Y080 TRAINING	Y000 NON-PART.
X2111000	TOPSOIL EXCAVATION	CU YD	12,560	12,560							
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	4,064	4,064							
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	29,429	29,429							
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	3,887	3,887							
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	6,262	6,262							
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	364	364							
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	110	110							
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	4	4							
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	365					365			
* X8730402	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 19 12 PAIR	FOOT	3,525						3,525		
* X8801300	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1					1			
* X8801310	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6					6			
* X8801395	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4					4			
* X8801400	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	5					5			
* X8801437	SIGNAL HEAD ,POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1					1			
XX003503	FLARED END SECTION REMOVAL	EACH	18	18							
XX003594	FORMED CONCRETE REPAIR	CU FT	5	5							
XX003817	GRATING FOR CONCRETE FLARED END SECTION 12"	EACH	1	1							
* XX004679	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8					8			
XX004852	BITUMINOUS DRIVEWAY PAVEMENT, SUPERPAVE	SQ YD	990	990							
XX005078	CATCH BASINS, TYPE C, 2' DIAMETER	EACH	20	20							
* XX005531	VMS 330 MODIFICATION	L SUM	1						1		
* XX005731	MAP PANEL MODIFICATION	EACH	1						1		
Z0000950	AGGREGATE FOR TEMPORARY ACCESS	TON	440	440							
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	38,146	38,146							
Z0002600	BAR SPLICERS	EACH	30		30						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
Z0019600	DUST CONTROL WATERING	UNIT	300	300							
Z0023800	FILLING EXISTING SEPTIC TANK	EACH	2	2							
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1							
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1							
Z0048865	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1							
Z0076600	TRAINEES	HOUR	1,000							1,000	
Z1101615	TOPSOIL PLACEMENT, 4"	SQ YD	76,625	76,625							
Z1101645	TOPSOIL PLACEMENT, 24"	SQ YD	1,022	1,022							
XX006195	STABILIZED BITUMINOUS PATH	SQ YD	1,908	1,908							
XY006581	BRICK SIGN	L SUM	1								1
XY006582	BRICK SIGN AND CONCRETE FOUNDATION REMOVAL	L SUM	1	1							
XY006583	TEMPORARY PIPE CULVERT	L SUM	1	1							
* XX005476	DUCTILE IRON WATER MAIN, 12" RESTRAINED JOINT TYPE	FOOT	115								115
XY006584	CURB STOP AND BOX TO BE REMOVED	EACH	7								7
XY006585	CURB STOP AND BOX 34"	EACH	7								7
* XX006266	CURB STOP AND BOX 1.5 INCH	EACH	1								1
XY006586	PVC CASING PIPE 30"	FOOT	50								50
XY006587	VALVE VAULTS, 6'-DIAMETER	EACH	2								2
XY006588	SLIP-ON FLAT BOTTOM CHECK VALVE, 12"	EACH	1	1							
XY006589	RELOCATE WOOD SIGN ASSEMBLY	EACH	1	1							
XY006590	RELOCATE CIVIL DEFENSE WARNING SIREN	L SUM	1	1							
XX006277	TEMPORARY SEDIMENT TRAP	EACH	2	2							
XX006285	PERIMETER EROSION BARRIER (SPECIAL)	FOOT	1,285	1,285							
XX006290	MANHOLES, TYPE A, 7'-DIAMETER	EACH	4	4							
* XY006591	PAVEMENT TEXTURING	SQ FT	5,620	5,620							
* XY006592	UNIT DUCT, WITH 2-1/C NO. 4, 2-1/C NO. 6, 2-1/C NO. 8 AND 1/C NO. 6 GROUND, 600V (XLP-TYPE USE), 2" DIA., POLYETHYLENE	FOOT	5,075						5,075		
* XY006593	UNIT DUCT, WITH 2-1/C NO. 4, 2-1/C NO. 6, 2-1/C NO. 8, 3-1/C NO. 10 AND 1/C NO. 6 GROUND, 600V (XLP-TYPE USE), 2" DIA., POLYETHYLENE	FOOT	140						140		
* XY006594	LIGHT STANDARD	EACH	2						2		
* XY006595	LIGHT STANDARD, INSTALLED	EACH	23						23		
* XY006596	DECORATIVE BASE FOR COMBINATION MAST ARM ASSEMBLY AND POLE	EACH	4						4		

* SPECIALTY ITEM