

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
332	(29, 29X) RS-2	GALLATIN/SALINE	15	3
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 98942

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	NHS-URBAN-STATE	NHS-RURAL-STATE	NHS-RURAL-STATE	NHS-RURAL-STATE
				80% FED / 20% STATE SALINE COUNTY	80% FED / 20% STATE SALINE COUNTY	80% FED / 20% STATE GALLATIN COUNTY	80% FED / 20% STATE SALINE COUNTY
				1000 QUANTITY	1000 QUANTITY	1000 QUANTITY	SFTY-2A QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	8903	2468	4947	1488	
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX D, N90	TON	8903	2468	4947	1488	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1	0.5		0.5	
35102000	AGGREGATE BASE COURSE TYPE B, 8"	SQ YD	637	162	185	290	
40600105	BITUMINOUS MATERIALS (PRIME COAT), SPECIAL	GALLON	13754	3610	7734	2410	
40600300	AGGREGATE (PRIME COAT)	TON	161	45	89	27	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	14	3.6	8.0	2.4	
X4060775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	4087	904	2450	733	
40600895	CONSTRUCTING TEST STRIP	EACH	2		1	1	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1474	506	736	232	
40600990	TEMPORARY RAMP	SQ YD	380	157	145	78	
40800040	INCIDENTAL BITUMINOUS SURFACE	TON	256	104	85	67	
44000002	BITUMINOUS SURFACE REMOVAL 1/2"	SQ YD	97533	21551	58490	17492	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	7881	7881			
44000030	BITUMINOUS SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	56	56			
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	449	140	240	69	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	2554	677	1294	583	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	53	53			
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	159		98	61	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2705	489	1816	400	
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	400				400
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4				4
* 63100167	TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (TANGENT)	EACH	6				6
63200310	GUARDRAIL REMOVAL	FOOT	250				250
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	2	6	1	
67100100	MOBILIZATION	L SUM	1	0.3	0.5	0.2	

PLOT DATE = 5/18/2006
 FILE NAME = D:\Program Development\Studies and Plans\Upstairs Design\Projects\US 45 3P-Eldorado\Plans\plans.dgn
 PLOT SCALE = 100.4337' / IN.
 USER NAME = thomashf