

F.A.S. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	17	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

• FAS 2882 (IL 37)/FAS 903
 • D9 CONT. MAINT. FY 07-5
 ••• FRANKLIN & WILLIAMSON

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FAS 903	FAS 903	FAS 2882 (IL 37)
				URBAN	RURAL	RURAL
				100% STATE	100% STATE	100% STATE
				WILLIAMSON COUNTY	WILLIAMSON COUNTY	FRANKLIN COUNTY
				1000	1000	1000
				QUANTITY	QUANTITY	QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	4,111.0	1,585.0	212.0	2,314.0
X4066418	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N90	TON	2,279.0			2,279.0
X4066430	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX D, N105	TON	1,745.0	1,543.0	202.0	
X7015000	CHANGEABLE MESSAGE SIGNS	CAL MO	1.0	0.8	0.2	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0		
40600105	BITUMINOUS MATERIALS (PRIME COAT) SPECIAL	GALLON	4,418.0	1,676.0	222.0	2,520.0
40600300	AGGREGATE (PRIME COAT)	TON	72.8	28.2	3.6	41.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	0.8	0.2	1.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	50 YD	462.0	204.0	51.0	207.0
40600990	TEMPORARY RAMP	50 YD	84.0	44.0	8.0	32.0
40800040	INCIDENTAL BITUMINOUS SURFACE	TON	50.0	9.0	2.0	39.0
44000002	BITUMINOUS SURFACE REMOVAL 1/2"	50 YD	41,746.0	12,586.0	2,446.0	26,714.0
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	50 YD	5,745.0	5,745.0		
44201798	CLASS D PATCHES, TYPE I, 13 INCH	50 YD	160.0	10.0		150.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	50 YD	150.0	50.0		100.0
44201807	CLASS D PATCHES, TYPE III, 13 INCH	50 YD	50.0	50.0		
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	50 YD	100.0	100.0		
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	FOOT	17,666.0			17,666.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	266.0	2.0		264.0
48201000	BITUMINOUS SHOULDERS	TON	227.0	191.0	36.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2.0	0.8	0.2	1.0
67100100	MOBILIZATION	L SUM	1.0	0.3	0.2	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.3	0.2	0.5
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0	0.3	0.2	0.5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,562.0	1,282.0	191.0	2,089.0
70300210	TEMPORARY PAVEMENT MARKING, LETTERS & SYMBOLS	50 FT	122.4	122.4		
70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	49,169.0	18,341.0	3,731.0	27,097.0
70300280	TEMPORARY PAVEMENT MARKING, LINE 24"	FOOT	69.0	69.0		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	50 FT	17,545.0	6,618.0	1,295.0	9,632.0
* 78001100	PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	50 FT	122.4	122.4		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	49,169.0	18,341.0	3,731.0	27,097.0
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	69.0	69.0		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	227.0	82.0	13.0	132.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	227.0	82.0	13.0	132.0

*SPECIALTY ITEMS

PLOT DATE : 4/28/2006
 PLOT SCALE : 1/8"=1'-0"
 USER NAME : mccordr