

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	ALEX./SALINE	12	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO 98983				
*VARIOUS				
** D-9 CONT. MAINT. FY 07-06				

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	CONSTRUCTION TYPE CODE - 1000							
		UNIT	TOTAL QUANTITIES	FUNDING 100 % STATE					
				ALEXANDER CO LOCATION 1	LOCATION 2	LOCATION 3	SALINE COUNTY LOCATION 4	LOCATION 5	LOCATION 6
X4066530	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX D, N105	TON	459	23	65	93	89	112	77
X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	TON	39	39					
X4066920	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N105	TON	75.5		2.1	18	11.1	33	11.3
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2.5	1.5	0.2	0.2	0.2	0.2	0.2
40600105	BITUMINOUS MATERIALS (PRIME COAT), SPECIAL	GALLON	487	26	74	96	92	120	79
40600300	AGGREGATE (PRIME COAT)	TON	8.1	0.5	1.2	1.6	1.5	2	1.3
40600990	TEMPORARY RAMP	SQYD	392	150	66	44	44	44	44
44000011	BITUMINOUS SURFACE REMOVAL 4 INCH	SQ YD	279	279					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	3429		826	538	786	667	612
48101200	AGGREGATE SHOULDERS, TYPE B	TON	61		9	12	11	16	13
67100100	MOBILIZATION	L SUM	1	0.17	0.17	0.17	0.17	0.16	0.16
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1		0.2	0.2	0.2	0.2	0.2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1020	264	153	144	141	186	132
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2747	54	434	560	537	700	462
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	18	18					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1291	141	196	235	226	295	198
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2747	54	434	560	537	700	462
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	18	18					
*88600100	DETECTOR LOOPS, TYPE 1	FOOT	213	213					

5/19/2006
 c:\pave\pctas\98983\205-vf\02206p1.dgn
 09:00:00 / IN
 p001

△ REV. 7-19 06

SUMMARY OF QUANTITIES