


SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
AR108158	1/C #8 5 KV UG CABLE IN UD	LF	14,485	
AR125415	MITL-BASE MOUNTED	EACH	29	
AR125441	TAXI GUIDANCE SIGN, 1 CHARACTER	EACH	1	
AR125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	2	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	1	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	1	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	6	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	12	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	3	
AR125906	REMOVE SPLICE CAN	EACH	1	
AR150510	ENGINEER'S FIELD OFFICE	LS	1	
AR156520	INLET PROTECTION	EACH	10	
AR201663	SAND MIX CRACK REPAIR	LF	1,200	
AR201670	CRACK CONTROL FABRIC	SY	24,500	
AR401610	BITUMINOUS SURFACE COURSE	TON	2,860	
AR401620	BIT. SURFACE COURSE - LEVELING	TON	2,530	
AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1	
AR401650	BITUMINOUS PAVEMENT MILLING	SY	5,800	
AR401655	BUTT JOINT CONSTRUCTION	SY	2,280	
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	2,900	
AR401915	REM AND REP BIT PAVEMENT - TYPE A	SY	1,140	
AR401916	REM AND REP BIT PAVEMENT - TYPE B	SY	500	
AR510900	REMOVE TIE DOWN	EACH	6	
AR603510	BITUMINOUS TACK COAT	GAL	3,900	
AR620520	PAVEMENT MARKING - WATERBOURNE	SF	7,030	
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	7,490	
AR705900	REMOVE UNDERDRAIN	LF	215	
AR705904	REMOVE UNDERDRAIN CLEANOUT	EACH	2	
AR800053	SOIL GUARD	SY	12,000	
AR800104	SHOULDER FILL	CY	800	
AR800894	RETROFIT EXISTING MITL OR TAXIWAY SIGN	EACH	120	
AR901510	SEEDING	ACRE	2.50	
AR905530	TOPSOILING	SY	8,800	

REVISIONS

NUMBER	BY	DATE



DUPAGE AIRPORT
 WEST CHICAGO, ILLINOIS
 REHABILITATE TAXIWAYS ALPHA AND CHARLIE

SUMMARY OF QUANTITIES

© copyright CMT, Inc.

CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 184-000613


DPA
 DuPage Airport

DESIGN BY:	JRL
DRAWN BY:	JRO
CHECKED BY:	CAL
APPROVED BY:	DLP
DATE:	06/09/06
JOB No:	04257-05

ILLINOIS PROJECT: DPA-3454
 A.I.P. PROJECT: 3-17-0017-B19