

SE002

DATE	REVISION	BY

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152480	SHOULDER ADJUSTMENT	S.Y.	4,556	
AR156520	INLET PROTECTION	EACH	4	
AR156531	EROSION CONTROL BLANKET	S.Y.	8,435	
AR201660	BITUMINOUS CRACK REPAIR	L.F.	425	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	24,000	
AR401610	BITUMINOUS SURFACE COURSE	TON	1,981	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	2,082	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	200	
AR402622	POROUS FRICTION COURSE, 0.10'	S.Y.	35,716	
AR510510	TIE DOWN	EACH	48	
AR510900	REMOVE TIE DOWN	EACH	42	
AR603510	BITUMINOUS TACK COAT	GAL.	11,931	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	21,078	
AR705410	POROUS BACKFILL	C.Y.	1,146	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	L.F.	6,875	
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	21	
AR705640	UNDERDRAIN CLEANOUT	EACH	5	
AR751909	REMOVE INSPECTION HOLE	EACH	1	
AR751940	ADJUST INLET	EACH	1	
AR751949	ADJUST INSPECTION HOLE	EACH	8	
AR901530	STRIP SEEDING	S.Y.	8,435	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES, INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	SUMMARY OF QUANTITIES FOR RUNWAY 18-36 OVERLAY
5	PROPOSED RUNWAY 18-36 CONSTRUCTION PLAN STA. 5+00 TO STA. 12+00
6	PROPOSED RUNWAY 18-36 CONSTRUCTION PLAN STA. 12+00 TO STA. 35+00
7	PROPOSED RUNWAY 18-36 CONSTRUCTION PLAN STA. 35+00 TO STA. 45+99
8	PROPOSED RUNWAY 18-36 MARKING PLAN STA. 5+00 TO STA. 12+00
9	PROPOSED RUNWAY 18-36 MARKING PLAN STA. 12+00 TO STA. 35+00
10	PROPOSED RUNWAY 18+36 MARKING PLAN STA. 35+00 TO STA. 45+99
11	SUMMARY OF QUANTITIES FOR APRON OVERLAY
12	PROPOSED APRON CONSTRUCTION PLAN
13	PROPOSED APRON PAVEMENT PREPARATION PLAN
14	PROPOSED APRON PLAN AND PROFILE
15	PROPOSED APRON STAKING PLAN
16	PROPOSED APRON MARKING AND TIE DOWN PLAN
17	PROPOSED APRON CROSS-SECTIONS STA.500+50 TO STA. 501+83
18	PROPOSED APRON CROSS-SECTIONS STA.502+00 TO STA. 503+25
19	PROPOSED APRON CROSS-SECTIONS STA.503+50 TO STA. 504+75
20	PROPOSED APRON CROSS-SECTIONS STA.505+00 TO STA. 506+25
21	PROPOSED APRON CROSS-SECTIONS STA.506+50
22	SUMMARY OF QUANTITIES FOR TAXIWAY "A" UNDERDRAINS
23	PROPOSED TAXIWAY "A" RIGHT UNDERDRAIN P&P STA. 1+00 TO STA. 8+00
24	PROPOSED TAXIWAY "A" LEFT UNDERDRAIN P&P STA. 1+00 TO STA. 8+00
25	PROPOSED TAXIWAY "B" RIGHT UNDERDRAIN P&P STA. 2+61.37 TO STA. 10+50
26	PROPOSED TAXIWAY "B" LEFT UNDERDRAIN P&P STA. 2+78.40 TO STA. 10+50
27	PROPOSED TAXIWAY "B" RIGHT UNDERDRAIN P&P STA. 10+50 TO STA. 19+00
28	PROPOSED TAXIWAY "B" LEFT UNDERDRAIN P&P STA. 10+50 TO STA. 19+00
29	PROPOSED TAXIWAY "B" RIGHT UNDERDRAIN P&P STA. 19+00 TO STA. 28+03.38
30	PROPOSED TAXIWAY "B" LEFT UNDERDRAIN P&P STA. 19+00 TO STA. 22+17
31	PROPOSED TAXIWAY "B" RIGHT UNDERDRAIN P&P STA. 100+00 TO STA. 103+25
32	PROPOSED TAXIWAY "B" LEFT UNDERDRAIN P&P STA. 100+00 TO STA. 103+25
33	PROPOSED DRAINAGE DETAILS

SHELBY COUNTY AIRPORT  
 SHELBYVILLE, ILLINOIS  
 I.L. PROJ.: 240-3615  
 A.I.P. PROJ.: 3-17-0093-B7

FILE PROJECT NO. 827-08APN	LAYOUT	CCC	05/01/06
FILENAME R-002FLP.DWG	DRAWN	CCC	05/01/06
SCALE NOT TO SCALE	REVIEWED	PAW	05/31/06
DATE 05/01/06			



OVERLAY RWY. & APN.  
 INSTALL UNDERDRAINS  
 SUMMARY OF QUANTITIES  
 AND  
 INDEX TO SHEETS