


# RUNWAY 18-36 POROUS FRICTION COURSE OVERLAY

SUMMARY OF QUANTITIES				
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR152480	SHOULDER ADJUSTMENT	S.Y.	2,834	
AR156531	EROSION CONTROL BLANKET	S.Y.	2,834	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	24,000	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	752	
AR402622	POROUS FRICTION COURSE, 0.10'	S.Y.	35,716	
AR603510	BITUMINOUS TACK COAT	GAL.	8,929	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	21,272	
AR901530	STRIP SEEDING	S.Y.	2,834	

SHELBYS COUNTY AIRPORT SHELBYSVILLE, ILLINOIS		DATE REVISION BY
ILL. PROJ.: 2HQ-3615 A.I.P. PROJ.: J-17-0093-B7		
H&E Project No. 827-06APN Drawings R-003FLP.DWG Scale NOT TO SCALE Date 05/01/06	LAYOUT CCC 05/01/06 DRAWN CCC 05/01/06 REVIEWED Y 18-36 OVERLAY 05/01/06	
 Hanson Professional Services Inc. 1525 South Sixth Street Springfield, Illinois 62703-2886 Offices Nationwide		
OVERLAY RWY. & APN. INSTALL UNDERDRAINS		
SUMMARY OF QUANTITIES FOR RUNWAY 18-36 OVERLAY		
<b>4</b>		
4 of 33 sheets		