

# INSTALL UNDERDRAINS ON TAXIWAYS "A" AND "B"

SUMMARY OF QUANTITIES				
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR156531	EROSION CONTROL BLANKET	S.Y.	3,056	
AR705410	POROUS BACKFILL	C.Y.	1146	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	L.F.	6,875	
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	21	
AR705640	UNDERDRAIN CLEANOUT	EACH	5	
AR751909	REMOVE INSPECTION HOLE	EACH	1	
AR901530	STRIP SEEDING	S.Y.	3,056	

JUL 05, 2006 8:52 PM RAW  
 I:\AIRPORTS\SHELBY\827-06APN\AIRPORT\SHEETS\R-005FLP.DWG - FLAP-LUD

DATE	REVISION	BY

SHelBY COUNTY AIRPORT  
 SHelBYVILLE, ILLINOIS  
 A.I.P. PROJ.: 3-17-0093-87  
 IL PROJ.: ZHQ-3615

USE Project No. 827-06APN	DATE	05/01/06
Revision R-005FLP.DWG	DATE	05/01/06
Scale NOT TO SCALE	DATE	05/01/06
Date 05/01/06	DATE	05/01/06
LAYOUT	CCC	05/01/06
DRAWN	CCC	05/01/06
REVIEWED BY	Y 18-36	05/01/06



OVERLAY RWY. & APN.  
 INSTALL UNDERDRAINS  
 SUMMARY OF QUANTITIES  
 FOR  
 TAXIWAY "A" UNDERDRAINS