


CONSTR. CODE
80% FED 20% ST

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	
				0005	RURAL
40600370	LONGITUDINAL JOINT SEALANT	FOOT	30159	30159	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30	
40600990	TEMPORARY RAMP	SQYD	170	170	
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MX "C", N70	TON	8444	8444	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	181	181	
42000070	PAVEMENT CONNECTOR (HMI) FOR BRIDGE APPROACH SLAB	SQYD	137	137	
44000100	PAVEMENT REMOVAL	SQYD	137	137	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 11/2"	SQYD	104030	104030	
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQYD	490	490	
44213200	SAWCUTS	FOOT	95	95	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	859	859	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	112	112	
50105220	PIPE CULVERT REMOVAL	FOOT	62	62	
542A1063	PIPE CULVERTS, CLASS A TYPE 2 18"	FOOT	62	62	



MODEL: SQO SHEET 02 (Sheet)
 FILE NAME: P:\GIS\Projects\DOT\Office\District 3\ORD Projects\3364MIS\CADD\3364MIS_SQO

USER NAME = timothy.pietech	DESIGNED -	REVISED -
PLOT SCALE = 0.1000000331in.	DRAWN -	REVISED -
PLOT DATE = 5/11/2023	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE 1 SHEET OF 4 SHEETS STA +.. TO STA +..

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	12021RS6	ROCKFORD	2	4
ILLINOIS FED. AID PROJECT			CONTRACT NO. 66M189	

