

EARTHWORK (FOR INFORMATION ONLY)						
LOCATION		EARTH EXCAVATION	EXCAVATION TO USED IN EMBARKMENT ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	FURNISHED EXCAVATION EARTHWORK BAL
STATION		CU YD	CU YD	CU YD	CU YD	CU YD
STA 50+00 TO STA 50+50		68	51	8	43	
STA 50+50 TO STA 51+00		107	80	7	73	
STA 51+00 TO STA 51+50		111	83	6	77	
STA 51+50 TO STA 52+00		82	62	5	57	
STA 52+00 TO STA 52+50		62	47	2	45	
STA 52+50 TO STA 53+00		72	54	1	53	
STA 53+00 TO STA 53+32		40	30		30	
STA 53+32 TO STA 53+50		12	9		9	
STA 53+50 TO STA 54+00		125	94	1	93	
STA 54+00 TO STA 54+50		227	170	2	168	
STA 54+50 TO STA 55+00		209	157	1	156	
STA 55+00 TO STA 55+74		359	269		269	
STA 55+74 TO STA 56+00		156	117		117	
STA 56+00 TO STA 56+50		302	227	1	226	
STA 56+50 TO STA 57+00		306	230	2	228	
STA 57+00 TO STA 57+50		308	231	2	229	
STA 57+50 TO STA 58+00		330	248	2	246	
STA 58+00 TO STA 58+50		353	265	3	262	
STA 58+50 TO STA 59+00		323	242	3	239	
STA 59+00 TO STA 59+50		158	119	2	117	
STA 59+50 TO STA 59+57		3	2		2	
STA 59+57 TO STA 60+00		81	61	1	60	
STA 60+00 TO STA 60+50		113	85	16	69	
STA 60+50 TO STA 61+00		44	33	31	2	
STA 61+00 TO STA 61+17		5	4	6		2
STA 61+17 TO STA 65+70				BRIDGE		
STA 65+70 TO STA 66+00		3	2	164		162
STA 66+00 TO STA 66+50		9	7	487		480
STA 66+50 TO STA 67+00		10	8	355		347
STA 67+00 TO STA 67+50		11	8	267		259
STA 67+50 TO STA 68+00		12	9	273		264
STA 68+00 TO STA 68+50		12	9	276		267
STA 68+50 TO STA 69+00		12	9	244		235
STA 69+00 TO STA 69+50		12	9	216		207
STA 69+50 TO STA 70+00		12	9	206		197
STA 70+00 TO STA 70+50		12	9	238		229
STA 70+50 TO STA 71+00		11	8	264		256
STA 71+00 TO STA 71+50		11	8	263		255
STA 71+50 TO STA 72+00		12	9	264		255
STA 72+00 TO STA 72+50		11	8	262		254
STA 72+50 TO STA 73+00		12	9	247		238
STA 73+00 TO STA 73+50		12	9	234		225
STA 73+50 TO STA 74+00		11	8	241		233
STA 74+00 TO STA 74+50		10	8	253		245
STA 74+50 TO STA 75+00		10	8	214		206
STA 75+00 TO STA 75+50		10	8	105		97
STA 75+50 TO STA 76+00		14	11	18		7
STA 76+00 TO STA 76+50		19	14		14	
STA 76+50 TO STA 77+00		15	11	6	5	
STA 77+00 TO STA 77+50		9	7	18		11
STA 77+50 TO STA 77+78		3	2	11		9
SUB-TOTAL		4231	3177	5228	2889	4940
TOTAL		4231	3177	5228	2889	4940

EARTHWORK SCHEDULE FOR INFORMATION ONLY							
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	FURNISHED EXCAVATION EARTHWORK BAL	TOPSOIL FURNISH AND PLACE, 4"	CHANNEL EXCAVATION
STATION	CU YD	CU YD	CU YD	CU YD	CU YD	SQ YD	CU YD
JOBSITE	4231	3177	5228	-2051	2051	13584	6737
TOTAL	4231	3177	5228	-2051	2051	13584	6737

1

MODEL: D:\p\h\l... FILE NAME: G:\P\GEN\WIN\W\06\DET&PLAN\S\0403\IL_17_91_Spoon River Structure Replacement_68698\BIDD\T Phase II CADD Drawings\IL_17_91_Cover_Sheets.dwg

USER NAME = Kyle.Harrison	DESIGNED -	REVISED KRH
PLOT SCALE = 100.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 7/17/2023	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
643	(11B)BR-1	STARK	115	19
CONTRACT NO. 68698				
ILLINOIS FED. AID PROJECT				