

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN	1000-2A	100% STATE			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	60	60					
40600300	AGGREGATE (PRIME COAT)	TON	300	300					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	710	710					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	425	425					
42001300	PROTECTIVE COAT	SQ YD	500	500					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	180	180					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1200	1200					
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	65300	65300					
44000114	BITUMINOUS REMOVAL OVER PATCHES 3 1/2"	SQ YD	2000	2000					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	180	180					
44000600	SIDEWALK REMOVAL	SQ FT	1200	1200					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2100	2100					
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	128	128					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	4500	4500					
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	100	100					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1200	1200					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	350	350					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	125	125					
55039700	STORM SEWERS TO BE CLEANED	FOOT	600	600					
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	26	26					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	8	8					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	126	126					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	48	48					
60624600	CORRUGATED MEDIAN	SQ FT	160	160					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN	1000-2A	100% STATE			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9600	9600					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	712.4	712.4					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	32050	32050					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4950	4950					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1200	1200					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	950	950					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16000	16000					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	712.4	712.4					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	32050	32050					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4950	4950					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	150	150					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1200	1200					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	950	950					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1250	1250					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1200	1200					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	5508	5508					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154.2	154.2					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	700	700					
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	7400	7400					

7/18/2005

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
BELVIDERE ROAD

*SPECIALTY ITEMS

PLOT DATE: 7/18/2005