

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	(B&14) R-3	WILL	390	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 60961				

### SUMMARY OF QUANTITIES

LOCATION OF WORK: U. S. ROUTE 30 - STA. 716+77.10 TO STA. 846+13.54

PAY ITEM NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL / 20% STATE		100% SUNNYLAND	80% FEDERAL / 20% STATE		100% MUNICIPALITY		80% FEDERAL / 20% STATE
				ROADWAY I000-2A	ROCK RUN & SUNNYLAND DRAIN BOX CULVERTS Y007	RETAINING WALL Y007	SANITARY DIST. Y060	TRAFFIC SIGNALS Y031-1F	<del>TRAINING Y080</del>	CREST HILL	JOLIET
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	8	8							
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	31	31							
60255500	MANHOLES TO BE ADJUSTED	EACH	35	5		12			18		
60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	1						1		
60260100	INLETS TO BE ADJUSTED	EACH	5	5							
60266600	VALVE BOXES TO BE ADJUSTED	EACH	34	9					25		
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	6							6	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	13	1		1			4	7	
60500040	REMOVING MANHOLES	EACH	17	17							
60500060	REMOVING INLETS	EACH	27	27							
60600605	CONCRETE CURB, TYPE B	FOOT	1540.9	1540.9							
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	50.0	50							
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1580.8	1580.8							
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	19165.8	19165.8							
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	54.7	54.7							
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	152.2	152.2							
60615400	PAVED DITCH, TYPE A-15	FOOT	591	591							
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	894	894							
60619600	CONCRETE MEDIAN TYPE SB.6-12	SQ FT	3862	3862							
60624600	CORRUGATED MEDIAN	SQ FT	1025	1025							
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1325.0	1325.0							
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4							
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4							
63200310	GUARDRAIL REMOVAL	FOOT	756	756							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24							
67100100	MOBILIZATION	L SUM	1	1							
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1							
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1							
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	372	372							
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2908	2908							
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	281	281							
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	23381	23381							
70300540	PAVEMENT MARKING TAPE, TYPE III, 6"	FOOT	913.7	913.7							

L:\DOT\00060602\design\comps\Summary of Quantities\SumQuan005.dgn

LEGEND:  
 NON-PARTICIPATING WORK  
 SPECIALTY ITEMS



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 US ROUTE 30  
 SHEET 5 OF 8  
 SCALE: N/A  
 DATE: 3/1/05  
 DRAWN BY: AMB  
 CHECKED BY: KDF/AMB