

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	598	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62302		*(1818, ETC, 2324.6-1P)R-9		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		90% FEDERAL / 10% STATE							S.N. 016-0142
			TOTAL QUANTITY	ROADWAY J000-2A	RETAINING WALLS Y007	S.N. 016-2625 X928-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	BRIDGE REPAIRS SFTY-2A	S.N. 016-1140
XX004201	PAVEMENT REINFORCEMENT 14"	SQ YD	146,650	146,650								
• XX004812	VIDEO TAPING OF SEWERS	FOOT	713	713								
XX005489	STEEL CASING 48"	FOOT	85	85								
Z0026420	STEEL CASING 60"	FOOT	259	259								
Z0066426	STEEL CASING 66"	FOOT	161	161								
Z0002600	BAR SPLICERS	EACH	277	20		257						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1								
□ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	42	42								
Z0018800	DRAINAGE SYSTEM	L SUM	1	1								
Z0018900	DRILL AND GROUT DOWEL BARS	EACH	6,494	6,494								
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	6					6				
Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW) TEST LEVEL 3	EACH	2					2				
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1					1				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	5					5				
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	489	489								
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.8								
Z0076600	TRAINEES	--- HOUR										
• X8100042	CONDUIT ENCASED, CONCRETE, 3" DIA., PVC	FOOT	1,133							1,133		
• X0325080	VIDEO TAPING OF MWRD CULVERT	FOOT	245			245						
X4810100	TEMPORARY SHOULDERS	SQ YD	6,990	6,990								
X0325081	CONCRETE SLAB HYDRO-DEMOLITION	SQ YD	237			237						
X6370927	CONCRETE BARRIER SINGLE FACE 72" (SPECIAL)	FOOT	166	166								
X0325082	CTA BARRIER REMOVAL	FOOT	21,813	21,813								
• X0325083	CTA FENCE	FOOT	22,921	22,834		87						
• X0325084	CTA GATES	EACH	24	24								
X0325085	TEMPORARY PAVEMENT (INTERSTATE)	SQ YD	10,717	10,717								
• X7011006	TRAFFIC CONTROL AND PROTECTION FOR ALTERNATE ROUTE SIGNING	LAL MD	10	10								
X0325086	TEMPORARY CTA BALLAST RETENTION	L SUM	1			1						
• X7330105	OVERHEAD SIGN STRUCTURE WALKWAY TYPE A	FOOT	56					56				
• X0950610	REMOVE AND RELOCATE EXISTING LIGHTING UNIT	EACH	5						5			
• X8210015	TEMPORARY LUMINAIRE, 400 WATT HPSV	EACH	5						5			

• - 4080
 • - SPECIALTY ITEM
 □ - NON-PARTICIPATING

BOWMAN, BARRETT & ASSOCIATES INC.
 CONSULTING ENGINEERS
 Chicago, Illinois
 312.228.0100
 www.bbainc.com

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 SB EXPRESS LANE RECONSTRUCTION
 SUMMARY OF QUANTITIES
 SCHEDULE

SCALE: NTS
 DATE: 07/07/05

DRAWN BY: RA
 CHECKED BY: JDC

S00-07

6/29/2005 5:05:42 PM