

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	598	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62302		1818, ETC, 2324.6-1PIR-8		

PAVEMENT, SHOULDERS, AND MEDIANS

STATION	TO STATION	CONT REINF PCC PVT 14 (SQ YD)	PAVT REINF (SQ YD)	PCC SHOULDERS 14 (SQ YD)	TEMP PAVEMENT (INTERSTATE) (SQ YD)	TEMP SHOULDERS (SQ YD)	STAB SUB- BASE 6 (SQ YD)	SUB GRAN MAT B 24 (SQ YD)	GEOTECH FAB F/GR STAB (SQ YD)	CONC MEDIAN SURF 6 SP (SQ YD)	PROTECTIVE COAT (SQ YD)	BIT SHLD SUPER 6 (SQ YD)
1367+00	1382+00	10242	10242	1235	51		11751	11751	11751		11528	
1382+00	1397+00	8536	8536	2559			11436	11436	11436		11095	36
1397+00	1412+00	6000	6000	3485			10077	10077	10077	13800	9489	
1412+00	1427+00	6000	6000	4234	219		10816	10816	10816		10453	
1427+00	1442+00	6000	6000	3360	569		8520	8520	8520		8259	
1442+00	1457+00	8356	8356	4568	1448		11989	11989	11989		11474	
1457+00	1472+00	8547	8547	2964	712		14085	14085	14085		13827	
1472+00	1487+00	8000	8000	3219	788		11874	11874	11874		11752	
1487+00	1502+00	8000	8000	3181	828		12261	12261	12261		12009	
1502+00	1517+00	10419	10419	3260	2096		16182	16182	16182	2471	15775	
1517+00	1530+00	5771	5771	2850	1892		10922	10922	10922	4071	10513	
1530+00	1542+00	5074	5074	2405	254	1593	7927	9478	7927		7479	
1542+00	1554+00	8171	8171	2410		624	10783	11425	10783		10580	
1554+00	1566+00	6400	6400	2463		1042	9038	10103	9038		8863	
1566+00	1578+00	6400	6400	2439	381	583	9002	10012	9002		8839	
1578+00	1590+00	5937	5937	2262	211	748	8366	9347	8366		8199	
1590+00	1602+00	6400	6400	2439		1112	9039	10160	9039		8839	
1602+00	1614+00	6400	6400	2289	406	620	8799	9851	8799		8689	
1614+00	1626+00	6400	6400	2146	743		8565	9332	8565		8546	
1626+00	1638+00	6400	6400	2439	120	669	9060	9803	9060		8839	
1638+00	BBA END	3197	3197	1215			4584	4412	4584		4412	
TOTAL		146651	146651	57423	10717	6990	215074	223837	215074	20342	209459	36

PAVEMENT AND SHOULDER REMOVAL

STATION	TO STATION	PAVEMENT REM (SQ YD)	PAVED SHLD REMOVAL (SQ YD)	APPROACH SLAB REM (SQ YD)
1367+00	1382+00	9680	1500	
1382+00	1397+00	13889	1500	
1397+00	1412+00	8605	1672	
1412+00	1427+00	8642	1886	
1427+00	1442+00	6330	3311	
1442+00	1457+00	10038	4037	
1457+00	1472+00	8475	3333	
1472+00	1487+00	8485	3061	
1487+00	1502+00	8429	3333	
1502+00	1517+00	10115	4163	
1517+00	1530+00	6449	4233	
1530+00	1542+00	6267	3398	
1542+00	1554+00	7884	3532	
1554+00	1566+00	6400	3190	
1566+00	1578+00	6400	3189	
1578+00	1590+00	6036	2615	219
1590+00	1602+00	6400	3160	
1602+00	1614+00	6400	3105	
1614+00	1626+00	6400	3090	
1626+00	1638+00	6400	2925	
1638+00	BBA END	3317	1543	
TOTAL		161041	61779	219

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



REVISIONS	
NAME	DATE

RSCH-01
ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
SB EXPRESS LANE RECONSTRUCTION
ROADWAY SCHEDULES
SCALE: 1"=N.T.S. DRAWN BY: RR
DATE: 07/07/05 CHECKED BY: JDC

06/29/2005 11:06:09 AM