

| | | | | |
|-----------------------|--------------|----------------|-----------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 55 | 2003-118 GRR | WILL | 14 | 3 |
| FED. ROAD DIST. NO. 1 | | ILLINOIS | HIGHWAY PROJECT | |
| D -91 -074 -05 | | CONTRACT 62884 | | |

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|---|--------|------------------|----------------------------------|--|--|--|--|
| CODE NO | ITEM | UNIT | | 90% FED. 10% STATE URBAN SFTY-3J | | | | |
| X0324589 | PIPE UNDERDRAIN OUTLET EXTENSION FOR 4" PIPE | EACH | 16 | 16 | | | | |
| 20200100 | EARTH EXCAVATION | CU YD | 437 | 437 | | | | |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 2332 | 2332 | | | | |
| 20400800 | FURNISHED EXCAVATION | CU YD | 1897 | 1897 | | | | |
| * 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 12590 | 12590 | | | | |
| * 25000210 | SEEDING, CLASS 2A | ACRE | 2.60 | 2.60 | | | | |
| * 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 235 | 235 | | | | |
| * 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 235 | 235 | | | | |
| * 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 235 | 235 | | | | |
| * 25100630 | EROSION CONTROL BLANKET | SQ YD | 12590 | 12590 | | | | |
| 48101100 | AGGREGATE SHOULDERS, TYPE A 12" | SQ YD | 5830 | 5830 | | | | |
| 48202800 | BITUMINOUS SHOULDERS SUPERPAVE 10" | SQ YD | 55 | 55 | | | | |
| 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" | EACH | 2 | 2 | | | | |
| 54247130 | GRATING FOR CONCRETE FLARED END SECTION 24" | EACH | 2 | 2 | | | | |
| 54248515 | CONCRETE COLLAR | EACH | 32 | 32 | | | | |
| 542A0229 | PIPE CULVERTS, CLASS A, TYPE 1 24" | FOOT | 8 | 8 | | | | |
| 60100060 | CONCRETE HEADWALL FOR PIPE DRAINS | EACH | 4 | 4 | | | | |
| 63000145 | STEEL PLATE BEAM GUARD RAIL, TYPE D (SPECIAL) | FOOT | 8235 | 8235 | | | | |
| 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 1 | 1 | | | | |
| 63100167 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) | EACH | 1 | 1 | | | | |
| 63304390 | TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1A | EACH | 1 | 1 | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 4 | 4 | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | |
| 78200405 | GUARDRAIL MARKERS | EACH | 30 | 30 | | | | |
| X0301893 | REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAIN | EACH | 16 | 16 | | | | |

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|--|--------|------------------|----------------------------------|--|--|--|--|
| CODE NO | ITEM | UNIT | | 90% FED. 10% STATE URBAN SFTY-3J | | | | |
| X6330105 | TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1 SPECIAL | EACH | 1 | 1 | | | | |
| X7011015 | TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) | L SUM | 1 | 1 | | | | |
| X7015000 | CHANGEABLE MESSAGE SIGN | CAL MO | 3 | 3 | | | | |
| Δ Z0029999 | IMPACT ATTENUATOR REMOVAL | EACH | 1 | 1 | | | | |
| Δ Z0030030 | IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH | 1 | 1 | | | | |
| Δ Z0030330 | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3 | EACH | 1 | 1 | | | | |

* SPECIALTY ITEMS

Δ SFTY-3N

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 55/ I-55
CATON FARM ROAD TO N/O BLACK ROAD

PLOT DATE: 6/14/2005