

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 330	2004-130I	WILL	14	3

CONTRACT: 62900

LOCATION OF WORK: 1) US 45 OVER NORTH BRANCH PRAIRIE CREEK, SN 099-0118
2) US 45 OVER PRAIRIE CREEK, SN 099-0119

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO.	DESCRIPTION	UNIT		SFTY -2A	
				Loc. 1: SN 099-0118	Loc. 2: SN 099-0119
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	91.9	83.6	8.3
50102400	CONCRETE REMOVAL	CU YD	13.7	5.2	8.5
50300100	FLOOR DRAINS	EACH	6		6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	13.7	5.2	8.5
50300300	PROTECTIVE COAT	SQ YD	33.7	19.5	14.2
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	2070	1065	1005
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2190	830	1360
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	303.5	193.5	110
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	867	494	373
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2	2
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	360	180	180
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	360	180	180
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2	1	1

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
(SHEET 1 OF 2)

Rev.