

Contract Number: 62912

Notes:

All Posts shall be normal to parapet.

All joints in rail shall be spliced per detail.

Provide 1- $\frac{1}{8}$ " and 2- $\frac{1}{16}$ " Aluminum Shims for 25% of the Posts. Rail elements shall be parallel to Grade-high spots will be ground and low spots shimmed.

This work shall be paid for at the contract unit price per foot for Removing and Re-erecting Existing Ralling.

Horizontal rail element & rail posts shown are for information only.

ALUMINUM RAILING DETAIL

F.A.P. RT. 343

COOK COUNTY

SN 016-0525