

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 326	107 CRC-PP-3	KANE	13	7

CLASS A: PAVEMENT PATCHING SCHEDULE
Northbound ILLINOIS ROUTE 47
GALENA BLVD. TO NORTH OF I-88 BRIDGE (SEAVEY RD.)

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
	0+00	GALENA BLVD.-START OF OMISSION/LIMITS					
	23+95	CENTERLINE-BLISS RD.					
	35+62	START OF CRC PAVEMENT-END OF OMISSION					
1	36+74				5 x 12	6.7	II
2	37+74	5 x 12	6.7	II			
3	38+09				20 x 6	13.3	II
4	38+78				15 x 6	10.0	II
5	40+46				15 x 6	10.0	II
6	41+91				29 x 6	19.3	III
7	45+29	15 x 12	20.0	III			
8	46+59				25 x 6	16.7	III
9	48+39				15 x 12	20.0	III
10	48+62				30 x 6	20.0	III
11	49+32				18 x 6	12.0	II
12	49+98				38 x 6	25.3	IV
	52+16	CENTERLINE-KEDEKA RD.					
13	53+11				10 x 6	6.7	II
14	53+55				34 x 6	22.7	III
15	54+22				22 x 6	14.7	II
16	55+29				56 x 6	37.3	IV
17	56+02				18 x 6	12.0	II
18	56+78				50 x 6	33.3	IV
19	57+95				34 x 6	22.7	III
20	60+22				12 x 12	16.0	III
21	68+67				12 x 12	16.0	III
22	71+48				20 x 12	26.7	IV
23	73+12				11 x 6	7.3	II
24	73+43				8 x 6	5.3	II
25	76+32				10 x 6	6.7	II
26	78+87				25 x 6	16.7	III
27	79+37				10 x 6	6.7	II
28	79+52				10 x 6	6.7	II
29	80+18				22 x 12	29.3	IV
30	81+17				15 x 12	20.0	III
	81+49	CENTERLINE-S. ENTRANCE WAUBONSEE DR.					
31	81+82				12 x 6	8.0	II
32	82+10				8 x 6	5.3	II

CLASS A: PAVEMENT PATCHING SCHEDULE CONTRACT 62943
Northbound ILLINOIS ROUTE 47
GALENA BLVD. TO NORTH OF I-88 BRIDGE (SEAVEY RD.)

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
33	82+52				42 x 6	28.0	IV
34	83+03	13 x 12	17.3	III	13 x 12	17.3	III
35	83+24	16 x 12	21.3	III			
36	83+45				21 x 12	28.0	IV
37	83+54	10 x 6	6.7	II			
38	83+95				18 x 12	24.0	III
39	84+19				18 x 6	12.0	II
40	84+66				12 x 6	8.0	II
41	85+88				50 x 6	33.3	IV
42	86+76				8 x 6	5.3	II
43	87+52				9 x 6	6.0	II
44	88+69				20 x 6	13.3	II
45	89+37				14 x 12	18.7	III
46	89+95	10 x 12	13.3	II			
47	90+50				34 x 6	22.7	III
48	91+25	12 x 12	16.0	III			
49	91+42	29 x 12	38.7	IV			
50	92+11				8 x 6	5.3	II
51	92+55	11 x 12	14.7	II	11 x 12	14.7	II
52	92+71				7 x 6	4.7	I
53	92+78	12 x 12	16.0	III			
54	93+08	27 x 12	36.0	IV			
55	94+10	19 x 12	25.3	IV			
56	94+34				21 x 6	14.0	II
57	94+37	43 x 12	57.3	IV			
58	94+71				21 x 6	14.0	II
59	95+79	19 x 12	25.3	IV			
60	96+85				21 x 6	14.0	II
61	97+62	11 x 12	14.7	II	11 x 12	14.7	II
62	98+05	39 x 12	52.0	IV			
63	98+35				5 x 12	6.7	II
	100+10	CENTERLINE-HARTER RD.					
64	101+23	16 x 12	21.3	III			
65	103+33	11 x 6	7.3	II			
66	104+64	18 x 12	24.0	III			
67	106+40	12 x 12	16.0	III			
68	106+67	12 x 12	16.0	III			

CLASS "A" PATCHING
(BOTH SCHEDULES)

ILLINOIS DEPARTMENT OF TRANSPORTATION
PAVEMENT PATCHING SCHEDULE