ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 326	107 CRC-PP-3	KANE	13	8

CLASS A: PAVEMENT PATCHING SCHEDULE

Northbound ILLINOIS ROUTE 47
GALENA BLVD. TO NORTH OF I-88 BRIDGE (SEAVEY RD.)

PATCH LOCATION NUMBER	STATION	LANE 1 SIZE (L X W)	LANE 1 AREA (SQ. YD.)	LANE 1 TYPE	LANE 2 SIZE (L X W)	LANE 2 AREA (SQ. YD.)	LANE 2 TYPE
69	106+72				12 x 12	16.0	III
70	108+69	13 x 12	17.3	III			
71	109+41	8 x 6	5.3	II			
72	109+61	14 x 6	9.3	II			
73	110+40	20 x 12	26.7	IV			
74	114+95	7 x 6	4.7	I			
75	115+70				16 x 12	21.3	III
76	116+11				8 x 6	5.3	II
77	117+08	10 x 6	6.7	II			
78	122+78	20 x 12	26.7	IV			
79	125+92	15 x 12	20.0	III			
	127+49	CENTERLINE-NORTH ENTRANCE-WAUBONSEE COLLEGE					
80	128+67				6 x 12	8.0	II
	134+79	END OF CRC PAVEMENT-START OF OMISSION					

CLASS "A" PATCHING

CLASS D: PAVEMENT PATCHING SCHEDULE

CONTRACT 62943

Northbound ILLINOIS ROUTE 47
GALENA BLVD. TO NORTH OF I-88 BRIDGE (SEAVEY RD.)

PATCH LOCATION NUMBER	STATION	LANE 1 SIZE (L X W)	LANE 1 AREA (SQ. YD.)	LANE 1 TYPE	LANE 2 SIZE (L X W)	LANE 2 AREA (SQ. YD.)	LANE 2 TYPE
	178+34	START OF JCP PAVEMENT-END OF OMISSION					
81	178+34	8 x 12	10.7	II			
82	179+39	4 x 12	5.3	II			
83	179+69	6 x 6	4.0	I			
84	180+44	9 x 6	6.0	II			
85	180+58	14 x 12	18.7	III			
86	180+84	6 x 12	8.0	II			
87	181+56	6 x 6	4.0	I			
88	182+18	6 x 6	4.0	I			
89	182+44	10 x 6	6.7	II			
90	183+22	6 x 12	8.0	II			
91	184+11	13 x 12	17.3	III			
92	184+40	20 x 6	13.3	II			
93	184+66	13 x 12	17.3	III			
94	184+88	4 x 12	5.3	II			
95	185+15	7 x 12	9.3	II			
96	185+28	14 x 12	18.7	III			
97	185+48	21 x 6	14.0	II			
98	185+69	10 x 12	13.3	II			
99	185+91	14 x 6	9.3	II			
100	186+11	12 x 6	8.0	II			
101	186+30	11 x 6	7.3	II			
102	186+47	12 x 6	8.0	II	12 x 12	16.0	III
103	186+87				5 x 12	6.7	II
104	187+13				5 x 12	6.7	II
105	187+23				27 x 12	36.0	IV
106	188+06				6 x 12	8.0	II
107	188+18				11 x 12	14.7	II
108	188+35				14 x 12	18.7	III
109	188+55				51 x 12	68.0	IV
110	189+12				17 x 12	22.7	III
111	189+61				6 x 12	8.0	II
112	189+80				11 x 12	14.7	II
113	190+10				12 x 6	8.0	II
114	190+33				15 x 12	20.0	III
115	190+59	15 x 6	10.0	II	15 x 12	20.0	III
116	190+80	9 x 6	6.0	II	9 x 12	12.0	II

CLASS "D" PATCHING

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT PATCHING SCHEDULE

△1 REV. SHEET 7/20/05 TEF