

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 326	107 CRC-PP-3	KANE	13	11

CLASS A: PAVEMENT PATCHING SCHEDULE

Southbound ILLINOIS ROUTE 47
NORTH OF I-88 BRIDGE (SEAVEY RD.) TO NORTH OF GALENA BLVD.

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
	78+29	START OF CRC PAVEMENT-END OF OMISSION					
227	80+13	13 x 12	17.3	III			
228	81+44				15 x 6	10.0	II
229	82+06				12 x 12	16.0	III
230	83+90				10 x 6	6.7	II
231	87+95	22 x 12	29.3	IV			
232	88+49	8 x 6	5.3	II			
233	89+50	12 x 12	16.0	III			
234	98+15				12 x 12	16.0	III
235	102+09				12 x 12	16.0	III
236	107+96	47 x 6	31.3	IV			
237	108+01				8 x 6	5.3	II
238	108+60	23 x 6	15.3	III	23 x 6	15.3	III
239	108+93				12 x 6	8.0	II
240	109+08				30 x 12	40.0	IV
241	111+04				50 x 12	66.7	IV
242	111+70	22 x 12	29.3	IV	17 x 12	22.7	III
243	112+19	20 x 6	13.3	II			
244	112+96				40 x 6	26.7	IV
	113+29	CENTERLINE-HARTER RD.					
245	115+64	25 x 6	16.7	III			
246	116+54				18 x 12	24.0	III
247	117+68				11 x 12	14.7	II
248	118+80				6 x 12	8.0	II
249	119+49				33 x 12	44.0	IV
250	119+86	19 x 6	12.7	II			
251	120+13				7 x 6	4.7	I
252	121+18				8 x 6	5.3	II
253	122+13	31 x 6	20.7	III			
254	122+36	11 x 6	7.3	II			
255	124+92				9 x 6	6.0	II
256	125+69	20 x 6	13.3	II			
257	128+33				10 x 6	6.7	II
258	128+55				14 x 12	18.7	III
259	130+37				11 x 6	7.3	II
260	131+54	7 x 6	4.7	I			
	132+65	CENTERLINE-WAUBONSEE RD.					

CLASS A: PAVEMENT PATCHING SCHEDULE

CONTRACT 62943

Southbound ILLINOIS ROUTE 47
NORTH OF I-88 BRIDGE (SEAVEY RD.) TO NORTH OF GALENA BLVD.

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
261	132+67				16 x 12	21.3	III
262	134+38				12 x 6	8.0	II
263	137+25				13 x 12	17.3	III
264	137+81	15 x 6	10.0	II	15 x 6	10.0	II
265	138+94	34 x 6	22.7	III	34 x 6	22.7	III
266	139+40				10 x 6	6.7	II
267	140+12				17 x 6	11.3	II
268	142+67	15 x 12	20.0	III			
269	143+13	42 x 12	56.0	IV			
270	143+61				15 x 6	10.0	II
271	144+06	29 x 12	38.7	IV			
272	144+12				12 x 6	8.0	II
273	145+63				13 x 6	8.7	II
274	148+86				8 x 6	5.3	II
275	152+56	15 x 12	20.0	III			
276	154+06	10 x 12	13.3	II	10 x 12	13.3	II
277	154+69				10 x 12	13.3	II
278	156+17				7 x 6	4.7	I
	161+59	CENTERLINE-KEDEKA RD.					
279	164+91				16 x 12	21.3	III
280	171+05				11 x 12	14.7	II
281	171+21				35 x 6	23.3	III
282	172+41				10 x 6	6.7	II
283	176+86	19 x 12	25.3	IV			
284	177+52	14 x 12	18.7	III			
285	182+88				15 x 6	10.0	II
286	183+79				12 x 6	8.0	II
287	184+48				15 x 6	10.0	II
	189+59	CENTERLINE-WHEELER RD.					
288	191+31	11 x 12	14.7	II			
289	192+98				13 x 12	17.3	III
290	194+13	24 x 12	32.0	IV			
291	196+43				12 x 12	16.0	III
292	196+60				10 x 12	13.3	II
293	197+70				14 x 12	18.7	III
294	197+90				14 x 12	18.7	III
295	198+57				34 x 12	45.3	IV

CLASS "A" PATCHING
(BOTH SCHEDULES)

ILLINOIS DEPARTMENT OF TRANSPORTATION
PAVEMENT PATCHING SCHEDULE