ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 326	107 CRC-PP-3	KANE	13	11A

CONTRACT 62943

CLASS A: PAVEMENT PATCHING SCHEDULE

Southbound ILLINOIS ROUTE 47
NORTH OF I-88 BRIDGE (SEAVEY RD.) TO NORTH OF GALENA BLVD.

PATCH LOCATION NUMBER	STATION	LANE 1 SIZE (L X W)	LANE 1 AREA (SQ. YD.)	LANE 1 TYPE	LANE 2 SIZE (L X W)	LANE 2 AREA (SQ. YD.)	LANE 2 TYPE
296	198+76	10 x 12	13.3	II			
297	198+93	12 x 6	8.0	II			
298	199+23				12 x 6	8.0	II
299	200+13	18 x 12	24.0	III			
	200+91	CENTERLINE-W. PARK AVE.					
300	204+86	6 x 12	8.0	II	6 x 12	8.0	II
	207+40	END OF CRC PAVEMENT-START OF OMISSION					
	213+54	CENTERLINE-GALENA BLVD-END OF OMISSION/LIMITS					

LOCATION CODE:

LT LANE - LEFT TURN LANE/ BAY (NEXT TO LANE 1)

RT LANE - RIGHT TURN LANE/ BAY (NEXT TO LANE 2/3)

CROSSOVER - MEDIAN CROSSOVER
(NEXT TO LANE 1)

CLASS "A" PATCHING

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT PATCHING SCHEDULE

△1 ADDED SHEET 7/20/05 TEF