

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1362	3200 RS-2	COOK	22	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	URBAN CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000 STATE					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8					
40600300	AGGREGATE (PRIME COAT)	TON	37.5	37.5					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	192	192					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	446	446					
42101300	PROTECTIVE COAT	SQ YD	135	135					
44000116	BITUMINOUS REMOVAL OVER PATCHES 4"	SQ YD	1220	1220					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600	600					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	266	266					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	266	266					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	355	355					
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	25	25					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	32	32					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	40	40					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	985	985					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19060	19060					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2375	2375					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1435	1435					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	URBAN CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000 STATE					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	165	165					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9635	9635					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19060	19060					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2375	2375					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1435	1435					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	165	165					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	230	230					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	230	230					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	570	570					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	1560	1560					
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	780	780					
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	18524	18524					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	57	57					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
LAWRENCE AVENUE
SUMMARY OF QUANTITIES

6/8/2005 6:40:39 AM