

62954

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100 %				
				STATE				
			I000-2A					
20200100	EARTH EXCAVATION	CU YD	1313	1313				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	113	113				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	715	715				
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	665	665				
25000210	SEEDING, CLASS 2A	ACRE	0.14	0.14				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	13	13				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	13	13				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	13	13				
25100630	EROSION CONTROL BLANKET	SQ YD	678	678				
28000300	TEMPORARY DITCH CHECKS	EACH	2	2				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5				
40600300	AGGREGATE (PRIME COAT)	TON	2.5	2.5				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	40	40				
44000100	PAVEMENT REMOVAL	SQ YD	417	417				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	300	300				
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	746	746				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	94	94				
48200600	BITUMINOUS SHOULDERS 8"	SQ YD	585	585				
60107600	PIPE UNDERDRAINS 4"	FOOT	934	934				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	30	30				
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	300	300				
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	4	4				
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1				
63200310	GUARDRAIL REMOVAL	FOOT	102	102				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1636	1636				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100 %				
				STATE				
			I000-2A					
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1446	1446				
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	70	70				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	144	144				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	24	24				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12				
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	48	48				
X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	1500	1500				
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	1000	1000				
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	166	166				
X4066658	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	1000	1000				
* X7240505	RELOCATE SIGN PANEL AND POST	EACH	8	8				
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	1857	1857				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
* 72000100	SIGN PANEL - TYPE 1	SQ. FT.	20	20				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1	1				
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	1000	1000				

*SPECIALTY ITEMS Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

6/9/2005 6:13:03 PM C:\projects\060905\060905.dwg