

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
346	124 N	LAKE	19	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62954				

EARTHWORK SCHEDULE

STATION	STATION LENGTH	EXCAVATION END AREA (S.F.)	EMBANKMENT END AREA (S.F.)	EXCAVATION (CU. YD.)	EXCAVATION USED AS EMBANKMENT (SHRINKAGE 15%) (CU. YD.)	EMBANKMENT (CU. YD.)	EARTHWORK BALANCE SURPLUS (+) OR SHORTAGE (-) (CU. YD.)	UNSUITABLE MATERIAL (CU. YD.)
115+08.03		14.76	0.00					
116+00	91.97	44.65	0.10	101.21	86.03	0.17		
117+00	100	34.53	0.04	146.63	124.64	0.26		
118+00	100	35.80	0.00	130.24	110.70	0.07		
119+00	100	36.90	0.00	134.60	114.41	0.00		
120+00	100	33.00	2.34	129.44	110.02	4.33		
120+70.05	70.05	33.63	1.95	86.43	73.47	5.57		
121+00	29.95	36.45	4.15	38.87	33.04	3.38		
122+00	100	47.83	0.00	156.07	132.66	7.69		
123+00	100	52.64	0.08	186.06	158.15	0.15		
124+00	100	52.10	0.00	193.96	164.87	0.15		
124+62.61	62.61	53.60	0.00	122.55	104.17	0.00		
SUBTOTAL				1426	1212.16	21.17	+ 1191	113

NOTE:

A THICKNESS OF 6 INCHES OF TOPSOIL STRIPPING SHALL BE USED FOR REMOVAL AND DESPOSAL OF UNSUITABLE MATERIAL.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. 346 (IL RTE. 41)
@ IL 173
SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY

PLOT DATE = 6/9/2005
FILE NAME = c:\projects\11000000\consult\10\124_124_124.dgn
SCALE = 1/8" = 1'-0"
USER NAME = jstevens