

F.A.I. RYE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
412	(50-5B)I-1	LASALLE	29	3
FED. ROAD DIST. NO.		ILLINOIS	STATE AID PROJECT	

### SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: **X081-2A**

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	200
42001500	<b>PCC BRIDGE APPROACH SHOULDER PAVT</b>	SQ YD	45
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	575
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	1714
48300500	PCC SHOULDER 10"	SQ YD	1708
50102400	CONCRETE REMOVAL	CU YD	31.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	31.2
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	157
50500725	JACK AND REPLACE BEARINGS	EACH	12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6354
60260100	INLETS TO BE ADJUSTED	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5
67100100	MOBILIZATION	L SUM	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1580
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	521
70400100	TEMPORARY CONCRETE BARRIER	FOOT	555
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	555
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1580
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	34
78300100	PAVEMENT MARKING REMOVAL	SQ FT	521
XX005128	STRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	85
XZ191205	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 3"	SQ YD	519
X0300136	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	29
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	29
X0322379	CONCRETE SEALER	SQ YD	73
X0322905	PCC I-BEAM REPAIRS	L SUM	1
Z0002600	BAR SPLICER	EACH	38
Z0006205	BRIDGE DECK HYDRO-SCARIFICATION 1 1/2"	SQ YD	519
Z0015595	DECK DRAIN EXTENSIONS	EACH	3
* Z0030250	IMPACT ATTENUATOR, TEMPORARY, NON-REDIRECTIVE, TEST LEVEL 3	EACH	1
* Z0030350	IMPACT ATTENUATOR, RELOCATE, NON-REDIRECTIVE, TEST LEVEL 3	EACH	1

\* SFTY-3N

**REVISED** PER ADDENDUM  
**7-19-2005**

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
 S.N. 050-0174  
 F.A.I. 412 NORTHBOUND  
 OVER C. & N.W. RAILROAD  
 SECTION (50-5B)I-1  
 STA. 1216 + 43.45

DATE 04/24/2005

DRAWN BY RW  
 CHECKED BY

MARCH 30, 2005  
 C:\PROJECTS\CM\106\CM303\DATA\LS.DGN