

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(46-2HB)I	KANKAKEE	10	3
STA. 1224+55.93 TO STA. 1226+60.23				

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE:

**SFTY-2A
URBAN
100% STATE
TOTAL
QUANTITY**

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
X0321468	PLUG EXISTING DECK DRAINS	EACH	8
X0322066	PROTECTIVE SHIELD (PERMANENT)	SQ YD	309
Z0015595	DECK DRAIN EXTENSIONS	EACH	12
Z0016000	DECK SLAB REPAIR (FULL DEPTH)	SQ YD	30
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	187

DATE: 04/12/05
FILE NAME: c:/projects/cm304/details.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
F.A.I. ROUTE 57 SECTION (46-2HB)I
KANKAKEE COUNTY
S.N. 046-0088
STA. 225 + 59.91

DATE 04/12/05 DRAWN BY RLW
CHECKED BY