

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313		WARREN	26	3
STA. 461+50		TO STA. 579+20		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• 04 SLIDE REPAIR 2004				

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	Y009 RURAL 100% STATE
20200100	EARTH EXCAVATION	CU YD	3,765	3,765
25000312	SEEDING, CLASS 4A	ACRE	0.7	0.7
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	60	60
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	60	60
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	60	60
25100630	EROSION CONTROL BLANKET	SQ YD	3,194	3,194
28000300	TEMPORARY DITCH CHECKS	EACH	2.0	2.0
28100225	STONE RIPRAP, CLASS B3	TON	291	291
28200200	FILTER FABRIC	SQ YD	2,032	2,032
67100100	MOBILIZATION	L SUM	1	1
70100305	TRAFFIC CONTROL & PROTECTION STANDARD 701400	L SUM	1	1
70100420	TRAFFIC CONTROL & PROTECTION STANDARD 701411	EACH	1	1
70100700	TRAFFIC CONTROL & PROTECTION STANDARD 701406	L SUM	1	1
Z0054500	ROCK FILL	TON	725	725

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 11/3/2004

DRAWN BY: BALSER
DESIGNED BY: PETERSON
CHECKED BY: