

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313		WARREN	26	4
STA. 461+75		TO STA. 579+20		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• 04 SLIDE REPAIR 2002				

SCHEDULE OF QUANTITIES

MOBILIZATION	
LOCATION	L. SUM
JOBSITE	1

EARTH EXCAVATION	
LOCATION	QTY. (CU YD)
LT. STA 461+75 TO STA. 465+50	2,963
RT. STA 573+25 TO STA. 579+20	802
TOTAL	3,765

SEEDING, CLASS 4A	
LOCATION	QTY. (ACRE)
LT. STA 461+75 TO STA 465+50	0.61
RT. STA 573+25 TO STA 579+20	0.05
TOTAL	0.66

NITROGEN FERTILIZER NUTRIENT	
LOCATION	QTY. (POUND)
LT. STA 461+75 TO STA 465+50	55
RT. STA 573+25 TO STA 579+20	5
TOTAL	60

PHOSPHORUS FERTILIZER NUTRIENT	
LOCATION	QTY. (POUND)
LT. STA 461+75 TO STA 465+50	55
RT. STA 573+25 TO STA 579+20	5
TOTAL	60

POTASSIUM FERTILIZER NUTRIENT	
LOCATION	QTY. (POUND)
LT. STA 461+75 TO STA 465+50	55
RT. STA 573+25 TO STA 579+20	5
TOTAL	60

STONE RIPRAP CLASS B3	
LOCATION	QTY. (TON)
LT. STA 461+75 TO STA 465+50	291
TOTAL	291

ROCK FILL	
LOCATION	QTY. (TON)
RT. STA 573+25 TO STA 579+20	725
TOTAL	725

EROSION CONTROL BLANKET	
LOCATION	QTY. (SQ YD)
LT. STA 461+75 TO STA 465+50	2,963
RT. STA 573+25 TO STA 579+20	231
TOTAL	3,194

FILTER FABRIC	
LOCATION	QTY. (SQ YD)
LT. STA 461+75 TO STA 465+50	582
RT. STA 573+25 TO STA 579+20	1,450
TOTAL	2,032

TRAFFIC CONTROL & PROTECTION STANDARD 701400	
LOCATION	QTY. (L. SUM)
JOB SITE	1

TEMPORARY DITCH CHECKS	
LOCATION	QTY. (EACH)
LT. STA 461+75	1.0
LT. STA 465+50	1.0
TOTAL	2.0

TRAFFIC CONTROL & PROTECTION STANDARD 701406	
LOCATION	QTY. (L. SUM)
JOBSITE	1

TRAFFIC CONTROL & PROTECTION STANDARD 701411	
LOCATION	QTY. (EACH)
ALONG RAMP D	1
TOTAL	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: 11/3/2004

DRAWN BY: BALSER
DESIGNED BY: PETERSON
CHECKED BY: _____