

SUMMARY OF QUANTITIES

| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|----------------|----------|--------|-----------------|--------------|
| 1678 | 6 MFT. 0 | EDGAR | 29 | 5 |

CONTRACT NO. 70467

LOCATION OF WORK:

SCOTTLAND ROAD

STA. 0+09.00

TO

STA. 105+45.00

100% STATE

F000

CONSTRUCTION TYPE CODE:

TOTAL

QUANTITY

| <u>CODE NO</u> | <u>ITEM</u> | <u>UNIT</u> | <u>TOTAL QUANTITY</u> |
|----------------|--|-------------|---------------------------|
| 35800100 | PREPARATION OF BASE | SQ YD | 3,128.0 |
| 35800200 | AGGREGATE BASE REPAIR | TON | 313.0 |
| 40300100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 6,451.0 |
| 40300300 | BITUMINOUS MATERIALS (COVER AND SEAL COATS) | GALLON | 8,214.0 |
| 40300500 | COVER COAT AGGREGATE | TON | 235.0 |
| 40300600 | SEAL COAT AGGREGATE | TON | 141.0 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 39.0 |
| 67100100 | MOBILIZATION | L SUM | 1.0 |
| 70101835 | TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22 | L SUM | 1.0 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 1,051.0 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 350.0 |
| * 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 3,274.0 |
| X4032500 | BITUMINOUS MATERIALS (COVER AND SEAL COATS), SPECIAL | GALLON | 4,694.0 |
| XX000125 | AGGREGATE BASE COURSE, TYPE B, SPECIAL | TON | 4,066.0 |
| Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1.0 |

* SPECIALTY ITEM