

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1771	25RS-7	LOGAN	8	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVING SCHEDULE

LOCATION	LENGTH (FOOT)	LT SHLD WIDTH (FOOT)	PAVEMENT WIDTH (FOOT)	RT SHLD WIDTH (FOOT)	BIT SURF REM (VD) (SQ YD)	BIT MATL PR CT (TON)	AGG PR CT (TON)	LEVEL BINDER (TON)	BIT SURF COURSE (TON)	INC BIT SURF (TON)
STA 634+34.00 TO STA 672+71.00	3,837.00	1.5	24.0	1.5	11,511.00	4.37	23.02	483.46	966.92	
STA 704+77.00 TO STA 708+73.00	396.00	1.5	24.0	1.5	1,188.00	0.45	2.38	49.90	99.79	
STA 729+35.00 TO STA 766+93.00	3,758.00	1.5	24.0	1.5	11,274.00	4.28	22.55	473.51	947.02	
STA 766+93.00 TO STA 769+60.00	267.00	1.5	24.0	9.0	1,023.50	0.39	2.05	42.99	85.97	
SIDEROADS & ENTRANCES					82.67	0.03	0.17			10.42
<b>TOTAL</b>					25,079.17	9.52	50.17	1,049.86	2,099.70	10.42

AGGREGATE SHOULDERS, TYPE B

LOCATION	LENGTH (FOOT)	LT SHLD WIDTH (FOOT)	RT SHLD WIDTH (FOOT)	AVE DEPTH (INCH)	QUANTITY (SQ YD)
STA 634+34.00 TO STA 672+71.00	3,837.00	3.0	3.0	2.0	291.33
STA 704+77.00 TO STA 708+73.00	396.00	3.0	3.0	2.0	30.07
STA 729+35.00 TO STA 769+60.00	4,025.00	3.0	3.0	2.0	305.60
<b>TOTAL</b>					627.00

PAINT PAVEMENT MARKING - LINE 5"

LOCATION	LENGTH (FOOT)	SKIP-DASH 5" YELLOW (FOOT)	EDGE LINES 5" WHITE (FOOT)	TOTAL (FOOT)
STA 634+34.00 TO STA 672+71.00	3,837.00	959.25	7,674.00	8,633.25
STA 704+77.00 TO STA 708+73.00	396.00	99.00	792.00	891.00
STA 729+35.00 TO STA 769+60.00	4,025.00	1,006.25	8,050.00	9,056.25
<b>TOTAL</b>				18,580.50

TEMPORARY RAMP

LOCATION	LENGTH (FOOT)	PAVEMENT WIDTH (FOOT)	AREA (SQ YD)
STA 634+34.00	5.00	27.0	15.00
STA 672+71.00	5.00	27.0	15.00
STA 704+77.00	5.00	27.0	15.00
STA 708+73.00	5.00	27.0	15.00
STA 729+35.00	5.00	27.0	15.00
STA 769+60.00	5.00	27.0	15.00
STA 708+14 RT - SIDEROAD	5.00	71.0	39.44
<b>TOTAL</b>			129.44

SHORT-TERM PAVEMENT MARKING

LOCATION	LENGTH (FOOT)	NO. OF APS	TOTAL LENGTH (FOOT)
STA 634+34.00 TO STA 672+71.00	383.70	3	1,151.10
STA 704+77.00 TO STA 708+73.00	39.60	3	118.80
STA 729+35.00 TO STA 769+60.00	402.50	3	1,207.50
<b>TOTAL</b>			2,477.40

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	LENGTH (FOOT)	AREA (SQ FT)
STA 634+34.00 TO STA 672+71.00	383.70	127.90
STA 704+77.00 TO STA 708+73.00	39.60	13.20
STA 729+35.00 TO STA 769+60.00	402.50	134.17
<b>TOTAL</b>		275.27

PLOT DATE = 5/19/2005  
 FILE NAME = S:\Projects\Myers\55 FR Millersville\Aschedule.dgn  
 PLOT SCALE = 50.0000' / IN.  
 USER NAME = mjers.jp

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULES OF QUANTITIES  
 FAS 1771 (OLD US 66)  
 SECTION 25RS-7  
 LOGAN COUNTY

SCALE: VERT.      DRAWN BY  
 HORIZ.              CHECKED BY  
 DATE