

F.A.U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1636	92-00037-03-PV	WILL.	33	3
STA.	TO STA.			
FED. ROAD DIST. NO.	LINE NO.	FED. AID PROJECT		

83680

S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUAN	STU QUAN	HIGH PRIORITY	CONSTRUCTION TYPE CODE			
							PAVEMENT	MARKINGS	SIGNS	LANDSCAPE
							1000-2A	SFTY-1D	Y002-1C	Y003
	Z3000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100					100
	X4073081	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH) SUPERPAVE, 10"	SQ YD	8515	8515		8515			
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	337	337		337			
	20100410	TREE REMOVAL, SPECIAL (OVER 15 UNITS DIAMETER)	UNIT	223	223		223			
	20101000	TEMPORARY FENCE	FOOT	200	200		200			
	20200100	EARTH EXCAVATION	CU YD	2613	2613		2613			
	20400800	FURNISHED EXCAVATION	CU YD	417	417		417			
	XX004553	POROUS GRANULAR EMBANKMENT, SUBGRADE	TON	300	300		300			
	20800150	TRENCH BACKFILL	CU YD	990	990		990			
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2115	2115		2115			
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10728	10728					10728
*	25000210	SEEDING, CLASS 2A	ACRE	1.2	1.2					1.2
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	108	108					108
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	108	108					108
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	108	108					108
*	25100115	MULCH, METHOD 2	ACRE	1.2	1.2					1.2
*	25100630	EROSION CONTROL BLANKET	SQ YD	1240	1240					1240
*	25200110	SODDING, SALT TOLERANT	SQ YD	5900	5900					5900
*	25200200	SUPPLEMENTAL WATERING	UNIT	75	75					75
	28000400	PERIMETER EROSION BARRIER	FOOT	2850	2850		2850			
	28000500	INLET AND PIPE PROTECTION	EACH	14	14		14			
	28100107	STONE RIPRAP, CLASS A4	SQ YD	45	45		45			
	28200200	FILTER FABRIC	SQ YD	45	45		45			
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	10129		10129	10129			
	35800100	PREPARATION OF BASE	SQ YD	8500	8500		8500			
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2000	2000		2000			
	40600300	AGGREGATE (PRIME COAT)	TON	37	37		37			
	44000100	PAVEMENT REMOVAL	SQ YD	7116		7116	7116			
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	567	567		567			
	42300100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH	SQ YD	92	92		92			
	50105210	REMOVE EXISTING CULVERTS	FOOT	315	315		315			
	54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	107	107		107			
	54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1		1			
	54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1		1			
	550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	338		338	338			
	550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	225		225	225			
	550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	501		501	501			
	550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	200		200	200			
	550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	1129		1129	1129			
	55101200	STORM SEWER REMOVAL 24"	FOOT	56	56		56			
	60201340	CATCH BASINS, TYPE A, 4' - DIAMETER, TYPE 24 FRAME AND GRATE	EACH	14		14	14			
	60221100	MANHOLES, TYPE A, 5' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7		7	7			
	60223100	MANHOLES, TYPE A, SPECIAL, 5' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		2			
	550A2380	STORM SEWER, RUBBER GASKET, CLASS A, TYPE 1 30"	FOOT	305		305	305			
	550A2580	STORM SEWER, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	200		200	200			

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE
FUNDING	04-28-03
REV. EASEMENT	09-14-04

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.U. 1636 RICHTON ROAD
 SUMMARY OF QUANTITIES

SCALE: VERT. NA
 HORIZ. NA
 DATE 03-07-08

DRAWN BY EC
 CHECKED BY PKB