

SUMMARY OF QUANTITIES

F.A.P. ROUTE	COUNTY SECTION	COUNTY	TOTAL SHEETS
336	99-00243-00-PV	KANE	268
CONTRACT NO.			3A
63782			
SUMMARY OF QUANTITIES			
F.H.W.A. REG.5 ILLINOIS PROJECT F-0336(008)			

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE													
				J000-2A ROADWAY STA	J000-2A ROADWAY STU	Y003-TEA LANDSCAPING STU	Y003-TEA LANDSCAPING CITY NON-PART.	Y030-1E LIGHTING STU	Y030-1E LIGHTING CITY NON-PART.	Y031-1F SIGNALS DEAN STREET STU (1)	Y031-1F SIGNALS IL ROUTE 84 STU (2)	Y031-1F SIGNALS INTERCONNECT STU (3)	Y045-BTPW,TEA UNDERPASS STU	Y060 SANITARY CITY NON-PART. (4)	Y060 WATER MAIN CITY NON-PART. (5)		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	251	142	109												
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	130	22	108												
20200100	EARTH EXCAVATION	CU YD	80,836	62,711	18,125												
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	12,800	7,900	4,900												
20800150	TRENCH BACKFILL	CU YD	21,108	12,119	910											509	7,570
20900320	POROUS GRANULAR BACKFILL, SPECIAL	TON	3,675													3,675	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	32,139	19,776	12,267											96	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	53,961			53,961											
21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	4,886				4,886										
21301084	EXPLORATION TRENCH 84" DEPTH	FOOT	300	200	100												
* 25000210	SEEDING, CLASS 2A	ACRE	4.6			4.6											
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	891			826	65										
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	891			826	65										
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	891			826	65										
* 25001750	SEEDING, CLASS 4 (SPECIAL)	ACRE	0.5			0.5											
* 25100115	MULCH, METHOD 2	ACRE	23.1			23.1											
* 25100630	EROSION CONTROL BLANKET	SQ YD	8,815			8,815											
* 25200110	SODDING, SALT TOLERANT	SQ YD	32,754			29,359	3,395										
25200200	SUPPLEMENTAL WATERING	UNIT	865			813	52										
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,422	1,272	150												
28000300	TEMPORARY DITCH CHECKS	EACH	5	5													
28000400	PERIMETER EROSION BARRIER	FOOT	7,538	5,800	1,738												
28000500	INLET AND PIPE PROTECTION	EACH	2	2													
28000510	INLET FILTERS	EACH	14	9	5												
28100105	STONE RIPRAP, CLASS A3	SQ YD	24	24													
28100107	STONE RIPRAP, CLASS A4	SQ YD	403	403													
28100109	STONE RIPRAP, CLASS A5	SQ YD	36	36													
28100111	STONE RIPRAP, CLASS A6	SQ YD	251	251													
28200200	FILTER FABRIC	SQ YD	690	690													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	21	13	8												
40600300	AGGREGATE (PRIME COAT)	TON	50	31	19												
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	467	467													
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	30,112	26,486	3,626												
42001300	PROTECTIVE COAT	SQ YD	52,030	41,720	10,310												
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	394	38	356												
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	75,757	45,118	30,639												
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	300	300													
42400460	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH, SPECIAL	SQ FT	1,394	609	785												
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	9,824	6,112	3,712												
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	16,064	13,781	2,283												
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	195	59	136												
44000300	CURB REMOVAL	FOOT	72														
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	17,631	12,820	4,811												
44000600	SIDEWALK REMOVAL	SQ FT	18,795	9,179	9,616												
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	1,100	1,100													
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	79	79													
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	56	45	11												
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	117	18	99												
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	406	209	197												
44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	33,552	23,753	9,799												
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	268	268													
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	127		127												
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	518	518													
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	35,880													35,880	
50900805	PEDESTRIAN RAILING	FOOT	97													97	
51000105	PIPE HANDRAIL	FOOT	170													170	

* SPECIALTY ITEM