

DRAINAGE STRUCTURE TABLE STA. 61+50 TO STA. 66+50

NO.	STA.	OFFSET	STRUCTURE TYPE/SIZE				FRAME & GRATE	RIM ELEV EP/FR	INVERT (N)	INVERT (S)	INVERT (E)	INVERT (W)
			MH	CB	INL	OTHER						
227	62+11	48.0' RT				PRC FES 12					786.15	
228	62+11	31.79' RT	A 4				24	788.94		785.95	785.95	
229	63+11	31.08' RT	A 4				24	789.58	785.64 EX	785.64 EX		

F.A.P. ROUTE	COUNTY SECTION	COUNTY	TOTAL SHEET
336	99-00243-00-PV	KANE	268
CONTRACT NO. 83782			99
UTILITY PLAN STA. 61+50 TO STA 66+50			
F.H.W.A. REG.5 ILLINOIS PROJECT F-0336(00B)			

KANE COUNTY CIRCUIT CLERK'S OFFICE



PIPE TABLE STA. 61+50 TO STA. 66+50

PIPE NO.	LOCATION FROM STR #	TO STR #	DESCRIPTION	DIA (IN)	L (FT)	S (%)	TRENCH BACKFILL	
							L (FT)	VOL (CY)
S208	227	228	SS 1 RCCP IV	12	9	1.35	2	0.4
S209	228	EX	SS 1 RCCP IV	12	5	1.35	5	0.7

