

TIME: 10:52:34 PM

DATE: 06/05/2005

FILENAME: s:\@sat\751-000\704\432\micross\sheet\gennotes.dgn

GENERAL NOTES

1. THE LOCATIONS OF THE VARIOUS UNDERGROUND UTILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE. THE CONTRACTOR SHALL USE SPECIAL CARE WHEN CONDUCTING CONSTRUCTION OPERATIONS NEAR THEM TO PREVENT DAMAGE.
2. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL J.U.L.I.E. AND THE VILLAGE OF OAK PARK PUBLIC WORKS (708-358-5700) FOR FIELD LOCATIONS OF VARIOUS UTILITIES.
3. THE CONTRACTOR SHALL COORDINATE VARIOUS CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.
4. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKER MONUMENTS UNTIL THE OWNER, AN AUTHORIZED AGENT, OR LAND SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR WILL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUB-SECTION MONUMENTS DISRUPTED BY HIS/HER OPERATIONS.
5. BARRICADES: ALL UNBALLASTED TYPE I AND TYPE II BARRICADES SHALL HAVE TWO (2) SANDBAGS ON THE BOTTOM RAIL. A TYPE III BARRICADE SHALL REQUIRE A MINIMUM OF FOUR (4) SANDBAGS.
6. THE CONTRACTOR SHALL ENSURE THAT POSITIVE DRAINAGE IS MAINTAINED AT ALL TIMES DURING AND AFTER REPLACEMENT OF COMBINATION CONCRETE CURB AND GUTTER. THE CONTRACTOR SHALL DETERMINE THE PROPOSED GRADE OF THE GUTTER LINE TO ENSURE POSITIVE DRAINAGE.
7. TEN FOOT TRANSITIONS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS TO EXISTING CURBS AND GUTTERS AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCIDENTAL TO THE CONTRACT.
8. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS FOR THE PROTECTION OF EXISTING PLANT MATERIAL FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL AND THE REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL DAMAGED BY THE CONTRACTOR SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS.
9. CONTRACTOR SHALL TAKE CARE TO PROTECT EXISTING LANDSCAPING AT LOCATIONS NOT SHOWN IN THE PLANS TO BE REMOVED AND AS DIRECTED BY THE ENGINEER. LANDSCAPING TO BE PROTECTED THAT IS DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPLACED IN KIND AT HIS/HER EXPENSE.
10. ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION AND THE VILLAGE OF OAK PARK.
11. THE CONTRACTOR SHALL BE REQUIRED TO MAINTAIN PEDESTRIAN AND VEHICULAR ACCESS AT ALL TIMES TO ALL PRIVATE AND COMMERCIAL PROPERTIES DURING THE CONSTRUCTION OF THIS PROJECT.
12. THE CONTRACTOR SHALL PROTECT AND PRESERVE ALL PARKING METERS ALONG THE PROJECT CORRIDOR. IF THE PARKING METERS ARE FOUND TO INTERFERE WITH CONSTRUCTION ACITIVITY, THEY SHALL BE CAREFULLY REMOVED FROM THEIR METAL SUPPORT POST, STORED, AND IMMEDIATELY REINSTALLED WHEN THE HAZARD NO LONGER EXISTS, OR AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL BE CAREFUL NOT TO DAMAGE THE SUPPORT OR FOUNDATION WHEN REMOVING THE ADJACENT SIDEWALK. ANY DAMAGE TO OR LOSS OF ANY COMPONENT SHALL BE REPLACED OR REPAIRED AT NO EXTRA COST.
13. THE VILLAGE OF OAK PARK WATER DEPARTMENT (708-445-3340 EXT. 3375) SHALL BE RESPONSIBLE FOR TURNING THE WATER MAIN VALVES ON AND OFF. THE CONTRACTOR IS NOT ALLOWED TO TURN THE VILLAGE OF OAK PARK OWNED WATER MAIN VALVES ON AND OFF. THE CONTRACTOR SHALL CONTACT THE VILLAGE OF OAK PARK FOR A WATER METER IF NECESSARY.

HIGHWAY STANDARDS


- 000001-04 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
- 424001-04 CURB RAMPS FOR SIDEWALKS
- 442201-01 CLASS C AND D PATCHES
- 606001-02 CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
- 701301-02 LANE CLOSURE 2L, 2W SHORT TIME OPERATIONS
- 701601-04 URBAN LANE CLOSURE MULTILANE 1W OR 2W WITH NON-TRANSVERSABLE MEDIAN
- 701606-04 URBAN LANE CLOSURE MULTILANE 2W WITH MOUNTABLE MEDIAN
- 701701-04 URBAN LANE CLOSURE MULTILANE INTERSECTION
- 701801-03 LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
- 702001-05 TRAFFIC CONTROL DEVICES
- 814001 CONCRETE HANDHOLES
- 857001 STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
- 877001-02 STEEL MAST ARM ASSEMBLY AND POLE
- 880006 TRAFFIC SIGNAL MOUNTING DETAILS
- 886001 DETECTOR LOOP INSTALLATION
- 886006 TYPICAL LAYOUTS FOR DETECTION LOOPS

DISTRICT STANDARDS

- BD-24 CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
- TC-10 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
- TC-14 TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
- TC-22 TEMPORARY INFORMATION SIGNING
- TS-05 DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAIL (4 SHEETS)

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1419	04-00239-00-TL	COOK	34	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

83792

	REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
	NAME	DATE	FAU 1419 MADISON STREET GENERAL NOTES, HIGHWAY STANDARDS, AND DISTRICT DETAILS	
SCALE: VERT. DRAWN BY RCB		DATE 06/05/2005 CHECKED BY RKK		