

REF #	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
CH	A47	LAKE	176	6
STA	TO STA			
03-00088-00-FP	ELIMIS	SURFACE TRANSPORTATION FUNDING		
CONTRACT NUMBER 83807				

ITEM NO.	CODE NO.	PAY ITEM	UNIT	TOTAL	FUNDING BREAKDOWN																
					LOCATION OF WORK																
					DEERFIELD PKWY/ BUFFALO GROVE RD	HIGHLAND GROVE DR	LIGHTING	DEERFIELD PKWY@ BUFFALO GROVE RD	DEERFIELD PKWY@ HIGHLAND GROVE DR	DEERFIELD PKWY@ FIRE STATION	DEERFIELD PKWY INTERCONNECT	DEERFIELD PKWY EVP	CONSTRUCTION TYPE CODE								
SUMMARY OF QUANTITIES		Y000-2A	Y030-1E	Y031-1F (1)	Y031-1F (2)	Y031-1F (3)	Y031-1F (4)	Y031-1F (5)													
181	89502200	* MODIFY EXISTING CONTROLLER	EACH	3																	
182	89502375	* REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1																	
183	89502380	* REMOVE EXISTING HANDHOLE	EACH	13																	
184	89502385	* REMOVE EXISTING CONCRETE FOUNDATION	EACH	9																	
185	A2004624	* TREE, GLEDITSIA TRIACANTHOS INERMIS (THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	38	38																
186	A2007924	* TREE, TILIA AMERICANA REDMOND (REDMOND AMERICANA LINDEN), 3" CALIPER, BALLED AND BURLAPPED	EACH	75	75																
187	A2C037G3	* TREE, MALUS CORONARIA (CRABAPPLE), CONTAINER GROWN, 3-GALLON	EACH	84	84																
188	XX002856	* RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM	L SUM	1																	1
189	XX002868	* TEMPORARY DITCH CHECKS (SPECIAL)	EACH	20	20																
190	XX003660	* FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM24F SM12F	FOOT	10,064																	10064
191	XX003662	* ELECTRIC CABLE IN CONDUIT, VIDEO, NO. 20 3C	FOOT	172						96	76										
192	XX004679	* PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4						2											
193	XX004680	* PEDESTRIAN SIGNAL HEAD, L.E.D., 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	7						3	4										
194	XX004878	* MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEM	L SUM	1	1																
195	XX004914	* TEMPORARY TRAFFIC SIGNAL SYSTEM	EACH	1																	1
196	XX005230	* VIDEO DETECTION SYSTEM COMPLETE INTERSECTION	L SUM	2						1	1										
197	XX005231	* REMOTE CONTROLLED VIDEO SYSTEM	L SUM	2						1	1										
198	XX206400	* MAILBOX POSTS	EACH	4																	
199	X0301576	* COAXIAL CABLE IN CONDUIT	FOOT	172						96	76										
200	X0322256	* TEMPORARY INFORMATION SIGNING	SQ FT	364	364																
201	X0322925	* ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	9,922																	9922
202	XX005659	* SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER	EACH	142	139																
203	X0712400	* TEMPORARY PAVEMENT	SQ YD	8,545	8545																
204	X4066414	* BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	67																	
205	X4066614	* BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	309																	
206	X4021000	* TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	7	7																
207	X4022000	* TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1																
208	X4403300	* CONCRETE MEDIAN REMOVAL	SQ FT	6,399	6399																
209	X6013600	* PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	15,412	14318																
210	X6063401	* COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	1,085																	1,085
211	X6700405	* ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	CAL M	15	15																
212	X7015050	* PORTABLE CHANGEABLE MESSAGE SIGN	CAL M	7	7																
213	X7800100	* PAINT PAVEMENT MARKING - RAISED MEDIAN	SQ FT	1,161	1161																
214	X8050015	* SERVICE INSTALLATION - POLE MOUNTED	EACH	3																	
215	X8730027	* ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,553																	
216	X8730250	* ELECTRIC CABLE IN CONDUIT NO. 20 3C, TWISTED, SHIELDED	FOOT	652																	
217	X8800020	* SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	14																	
218	X8800035	* SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	7																	
219	X8800040	* SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	6																	
220	X8800045	* SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	6																	
221	X8950200	* REBUILD EXISTING HANDHOLE	EACH	1																	
222	Z0001050	* AGGREGATE SUBGRADE 12"	SQ YD	55,204	54421																
223	Z0019600	* DUST CONTROL WATERING	UNIT	150	150																
224	Z0044700	* PRESSURE CONNECTION 8" X 6"	EACH	4	2																
225	Z0045300	* PRESSURE CONNECTION 16" X 6"	EACH	1	1																
226	Z0076600	** TRAINEES	HOUR	1,000	1000																
227	XX006357	* ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 16 5 1/2 PAIR	FOOT	1,718																	
228	X0322131	* EMERGENCY VEHICLE PREEMPTION PUSHBUTTON ASSEMBLY	EACH	1																	
229	XX006358	* VIDEO TRANSMISSION SYSTEM (SPECIAL)	EACH	2																	
230	XX005937	* LED INTERNALLY ILLUMINATED STREET NAME SIGN	EACH	8																	
231	XX006359	* UNIT DUCT, WITH 2-1/2" #6 AND 1-1/2" #8 GROUND, 600V (XLP-TYPE USE), 2" DIA., POLYETHYLENE	FOOT	13,100																	
232	XX006360	* UNIT DUCT, WITH 3-1/2" #6 AND 1-1/2" #8 GROUND, 600V (XLP-TYPE USE), 2" DIA., POLYETHYLENE	FOOT	750																	
233	XX006361	* UNIT DUCT, WITH 4-1/2" #6 AND 2-1/2" #8 GROUND, 600V (XLP-TYPE USE), 2" DIA., POLYETHYLENE	FOOT	300																	
234	XX006362	* UNIT DUCT, WITH 2-1/2" #6 AND 1-1/2" #8 GROUND AND 3-1/2" #12 AND 1-1/2" #12 GROUND, 600V (XLP-TYPE USE), 2" DIA., POLYETHYLENE	FOOT	300																	
235	XX006363	* ELECTRIC CABLE, #2/0 STRANDED BARE COPPER, GROUND	FOOT	450																	
236	X0321478	* MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1																	
237	X8386683	* BREAKAWAY DEVICE	EACH	71																	
238	XX006364	* PHOTOCELL SHORTING CAP	EACH	32																	
239	X0324637	* BASE COVER, LIGHT POLE	EACH	22																	
240	XX006365	* EXISTING FIXTURE MAINTENANCE	EACH	35																	
241	XX006366	* CATCH BASINS, TYPE C, TYPE 18 FRAME AND GRATE	EACH	1	1																
242	XX006367	* CDS UNIT	EACH	2	2																
243	XX006367	* INLET AND OUTLET PROTECTION	EACH	46	46																
244	XX006368	* RESTRICTED DEPTH CATCH BASINS, 4'-DIAMETER, TYPE 12 FRAME AND GRATE	EACH	1																	
245	XX006369	* SAWED CONTRACTION JOINTS (SUPPLEMENTARY)	FOOT	300	300																
246	424 00 800	* DETECTABLE WARNINGS	SQ FT	1,900	1900																

* DENOTES SPECIALTY ITEMS
 ** DENOTES CONSTRUCTION CODE TYPE Y080

REVISIONS	
NAME	DATE

VILLAGE OF BUFFALO GROVE
SUMMARY OF QUANTITIES
 DEERFIELD PARKWAY IMPROVEMENT

DATE: 6/2/2005
 DESIGNED BY: STC
 TECHNICIAN: JRR
 CHECKED BY: RTM