

FILE #	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH	A47	LAKE	176	8
STA.	TO STA.			
03-0008-00-FP	ALIGN	SURFACE TRANSPORTATION FUNDING		
CONTRACT NUMBER 83807				

SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION													
Deerfield Parkway, Buffalo Grove Road, Highland Grove Drive													
STATION	DISTANCE	EARTH EXCAVATION (CUT)	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL (PGE)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION	EARTH EXCAVATION (SPECIAL)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)
31+00		68	0	0	15								
	50					34	0	0	21	1,700	0	0	1,025
31+50		0	0	0	26								
	50					32	0	0	22	1,575	0	0	1,075
32+00		63	0	0	17								
	50					70	0	0	15	3,500	0	0	750
32+50		77	0	0	13								
	50					83	0	0	13	4,125	0	0	650
33+00		88	0	0	13								
	50					102	0	0	12	5,075	0	0	600
33+50		115	0	0	11								
	50					122	0	0	10	6,075	0	0	475
34+00		128	0	0	8								
	50					152	0	0	9	7,600	0	0	425
34+50		176	0	0	9								
	50					148	0	0	5	7,400	0	0	225
35+00		120	0	0	0								
	50					112	0	0	0	5,575	0	0	0
35+50		103	0	0	0								
	50					125	9	9	5	6,225	425	425	250
36+00		146	17	17	10								
	50					133	15	15	13	6,650	750	750	625
36+50		120	13	13	15								
	50					115	13	13	15	5,725	650	650	725
37+00		109	13	13	14								
	50					99	13	13	15	4,925	650	650	725
37+50		88	13	13	15								
	50					73	7	7	13	3,650	325	325	625
38+00		58	0	0	10								
	50					54	0	0	12	2,675	0	0	575
38+50		49	0	0	13								
	50					63	0	0	12	3,125	0	0	575
39+00		76	0	0	10								
	50					82	0	0	10	4,100	0	0	475
39+50		88	0	0	9								
	50					82	0	0	11	4,075	0	0	525
40+00		75	0	0	12								
	50					70	0	0	11	3,475	0	0	525
40+50		64	0	0	9								
	50					53	0	1	11	2,650	0	50	525
41+00		42	0	2	12								
	50					30	0	3	13	1,475	0	125	650
41+50		17	0	3	14								
	50					16	0	6	17	775	0	300	825
42+00		14	0	9	19								
	50					14	0	14	21	700	0	675	1,050
42+50		14	0	18	23								
	50					12	0	20	25	575	0	1,000	1,225
43+00		9	0	22	26								
	50					10	18	29	27	475	875	1,425	1,325
43+50		10	35	35	27								
	50					12	34	34	25	575	1,675	1,675	1,225
44+00		13	32	32	22								
	50					24	31	31	20	1,175	1,525	1,525	1,000
44+50		34	29	29	18								
	50					54	28	28	21	2,675	1,400	1,400	1,050
45+00		73	27	27	24								
	50					94	26	26	24	4,675	1,300	1,300	1,175
45+50		114	25	25	23								
	50					116	22	22	25	5,800	1,100	1,100	1,250

REVISIONS	
NAME	DATE

VILLAGE OF BUFFALO GROVE

**SCHEDULE OF QUANTITIES**

**DEERFIELD PARKWAY IMPROVEMENT**

DATE: 6/2/2005  
DESIGNED BY: STC  
TECHNICIAN: JRR  
CHECKED BY: RTM