

FILE#	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH	A47	LAKE	176	9
STA.	TO STA.			
03-00088-00-PP	ELAND	SURFACE TRANSPORTATION FUNDING		
CONTRACT NUMBER 83807				

SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION													
Deerfield Parkway, Buffalo Grove Road, Highland Grove Drive													
STATION	DISTANCE	EARTH EXCAVATION (CUT)	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL (PGE)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION	EARTH EXCAVATION (SPECIAL)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SPECIAL	FURNISHED EXCAVATION
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)
46+00	50	118	19	19	27	116	17	17	27	5,800	825	825	1,325
46+50	50	114	14	14	26	127	7	7	13	6,350	350	350	650
47+00	50	140	0	0	0	108	0	0	4	5,375	0	0	175
47+50	50	75	0	0	7	69	0	0	8	3,450	0	0	400
48+00	50	63	0	0	9	64	0	0	9	3,175	0	0	450
48+50	50	64	0	0	9	72	0	0	10	3,575	0	0	475
49+00	50	79	0	0	10	82	0	0	11	4,075	0	0	525
49+50	50	84	0	0	11	89	0	0	14	4,450	0	0	675
50+00	50	94	0	0	16	98	0	0	19	4,900	0	0	950
50+50	50	102	0	0	22	100	0	0	22	5,000	0	0	1,075
51+00	50	98	0	0	21	107	0	0	22	5,350	0	0	1,075
51+50	50	116	0	0	22	120	0	0	22	5,975	0	0	1,100
52+00	50	123	0	0	22	113	0	0	22	5,625	0	0	1,100
52+50	50	102	0	0	22	82	0	0	25	4,075	0	0	1,250
53+00	50	61	0	0	28	61	0	0	29	3,025	0	0	1,450
53+50	50	60	0	0	30	63	0	0	29	3,150	0	0	1,450
54+00	50	66	0	0	28	65	0	0	31	3,225	0	0	1,550
54+50	50	63	0	0	34	83	0	0	29	4,150	0	0	1,450
55+00	50	103	0	0	24	98	13	13	23	4,900	625	625	1,125
55+50	50	93	25	25	21	105	25	25	23	5,250	1,250	1,250	1,150
56+00	50	117	25	25	25	126	25	25	24	6,275	1,250	1,250	1,175
56+50	50	134	25	25	22	133	25	25	24	6,650	1,250	1,250	1,200
57+00	50	132	25	25	26	129	25	25	32	6,425	1,250	1,250	1,600
57+50	50	125	25	25	38	144	29	29	25	7,175	1,450	1,450	1,225
58+00	50	162	33	33	11	137	17	17	6	6,850	825	825	275
58+50	50	112	0	0	0	89	0	0	22	4,425	0	0	1,100
59+00	50	65	0	0	44	79	0	0	42	3,925	0	0	2,100
59+50	50	92	0	0	40	66	0	0	42	3,300	0	0	2,100
60+00	50	40	0	0	44	40	0	3	41	1,975	0	125	2,050
60+50	50	39	0	5	38	44	0	8	38	2,200	0	400	1,900

REVISIONS	
NAME	DATE

VILLAGE OF BUFFALO GROVE
SCHEDULE OF QUANTITIES
DEERFIELD PARKWAY IMPROVEMENT

DATE: 6/2/2005
DESIGNED BY: STC
TECHNICIAN: JRR
CHECKED BY: RTM