

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5352	04-00168-00-RS	DEKALB	67	6
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT W-50173				

CODE #	ITEM	UNIT	QUANTITY
CONSTRUCTION CODE 1000			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42
20200100	EARTH EXCAVATION	CU YD	2723
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	500
20700300	POROUS GRANULAR EMBANKMENT, SPECIAL	TON	770
20800150	TRENCH BACKFILL	CU YD	619
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10523
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	100
25000350	SEEDING, CLASS 7	ACRE	2
25100630	EROSION CONTROL BLANKET	SQ YD	1000
25200100	SODDING	SQ YD	10523
25200200	SUPPLEMENTAL WATERING	UNIT	106
28000300	TEMPORARY DITCH CHECKS	EACH	8
28000400	PERIMETER EROSION BARRIER	FOOT	690
28000500	INLET AND PIPE PROTECTION	EACH	79
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	7398
35101400	AGGREGATE BASE COURSE, TYPE B	TON	325
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10
40600300	AGGREGATE (PRIME COAT)	TON	83
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	36
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4462
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	872
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	4392
44000100	PAVEMENT REMOVAL	SQ YD	672
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	832
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1120
44000600	SIDEWALK REMOVAL	SQ FT	5925
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	97
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	317
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	100
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	484
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	7750
50105210	REMOVE EXISTING CULVERTS	FOOT	543
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3
55019500	STORM SEWERS, TYPE 1, RCCP, CLASS IV 12"	FOOT	465
55019600	STORM SEWERS, TYPE 1, RCCP, CLASS IV 15"	FOOT	112
55021600	STORM SEWERS, TYPE 2, RCCP, CLASS III 12"	FOOT	1577
55021700	STORM SEWERS, TYPE 2, RCCP, CLASS III 15"	FOOT	195
* 56106300	ADJUSTING WATER MAIN 6"	FOOT	100
* 56106400	ADJUSTING WATER MAIN 8"	FOOT	100
* 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	100

CODE #	ITEM	UNIT	QUANTITY
CONSTRUCTION CODE 1000			
* 56300300	ADJUSTING WATER SERVICE LINES	FOOT	100
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	1
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	9
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	10
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	5
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	17
60210200	CATCH BASINS, TYPE C, SPECIAL, TYPE 11 FRAME AND GRATE	EACH	7
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	8
60239600	INLETS, TYPE A, SPECIAL, TYPE 11 FRAME AND GRATE	EACH	3
60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3
60255500	MANHOLES TO BE ADJUSTED	EACH	15
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	9
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2
60266600	VALVE BOXES TO BE ADJUSTED	EACH	14
60266910	VALVE BOXES TO BE REMOVED	EACH	7
60500050	REMOVING CATCH BASINS	EACH	5
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2370
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION, SPECIAL	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1500
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	500
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	63
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13939
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2165
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	960
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	369
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	63
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	13939
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	2165
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	960
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	369
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	6
X0323389	STORM SEWER CONNECTION	EACH	1
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	6811
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	2535
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	2596
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	500
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0041700	PLUG EXISTING STORM SEWERS	EACH	4
42400800	DETECTABLE WARNINGS	SQ FT	392

* SPECIALITY ITEMS