

THERMOPLASTIC PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	4 INCH			12 INCH		24 INCH	LETTERS AND SYMBOLS
	WHITE FOOT	YELLOW FOOT	DOUBLE YELLOW FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	
IL 148							
112+37 LT (IL 148) TO 2+52.37 LT (GRAND ROAD) EOP	339						
112+37 RT (148) TO 2+00 RT (McCREE ROAD) EOP	280						
112+37 TO 113+73.4 - WEST EDGE OF LTL			137				
112+37 TO 113+84.7 - EAST EDGE OF LTL	148						
112+45 - "ONLY"							20.8
113+55 LT TO 114+01.4 LT - MEDIAN	155			36			
112+67 - LEFT ARROW							15.6
113+60 - STOP BAR						18	
113+73.4 - STOP BAR						14	
113+77.4 RT TO 113+96.2 RT - MEDIAN	68			33			
113+81.3 - STOP BAR						18	
113+84.7 - STOP BAR						24	
114+39.3 LT TO 115+06.1 - MEDIAN	222			112			
114+77.8 - STOP BAR						24	
114+77.8 TO 117+06 - WEST EDGE OF LTL	229						
114+92.1 - STOP BAR						14	
114+92.1 TO 117+06 - EAST EDGE OF LTL			214				
115+06.1 TO 117+80 - EAST EDGE OF RTL	275						
116+58 - LEFT ARROW							15.6
116+80 - "ONLY"							20.8
117+06 TO 119+00 - TAPER			388		82		
GRAND ROAD							
0+53 - STOP BAR						13	
0+53 TO 2+45.77 - SOUTH EDGE OF LTL	173						
0+92 - STOP BAR						12	
0+92 TO 2+52.37 - NORTH EDGE OF RTL & TAPER			185				
1+01 - STOP BAR						18	
1+77 - LEFT ARROW							15.6
1+99 - "ONLY"							20.8
2+52.37 RT (GRAND ROAD) TO 119+00 LT (IL 148) EOP	610						
McCREE ROAD							
0+43.42 TO 1+90 - MEDIAN			299		41		
0+53 - STOP BAR						11	
0+58 - STOP BAR						14	
2+00 LT (McCREE ROAD) TO 119+00 RT (IL 148) EOP	604						
SUBTOTAL							
	3103	0	2446	181	123	180	109
TOTAL							
		5549		304		180	109