


**SUMMARY OF QUANTITIES**

ITEM NUMBER	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
AR108082	1/C #2 XLP-USE	LF	300	
AR110214	4" STEEL DUCT, DIRECT BURY	LF	84	
AR110314	4" STEEL DUCT, JACKED	LF	175	
AR110315	5" STEEL DUCT, JACKED	LF	45	
AR110550	SPLIT DUCT	LF	18	
AR127420	GLIDESLOPE	LS	1	
AR127430	SHELTER BUILDING	EACH	2	
AR127450	MALSR INSTALLATION	LS	1	
AR150510	ENGINEERS FIELD OFFICE	LS	1	
AR152410	UNCLASSIFIED EXCAVATION	CY	1,875	
AR152442	OFFSITE BORROW EXCAVATION	CY	350	
AR156513	SEPARATION FABRIC	SY	5,700	
AR156510	SILT FENCE	LF	5,115	
AR161614	CLASS C GATE-14'	EACH	1	
AR161624	CLASS C GATE-24'	EACH	2	
AR161900	REMOVE CLASS C FENCE	LF	62	
AR162506	CLASS E FENCE 6'	LF	241	
AR162605	CLASS E GATE-5'	EACH	1	
AR162614	CLASS E GATE-14'	EACH	1	
AR209608	CRUSHED AGG. BASE COURSE - 8"	SY	5,700	
AR401610	BITUMINOUS SURFACE COURSE	TON	850	
AR602510	BITUMINOUS PRIME COAT	GAL	545	
AR603510	BITUMINOUS TACK COAT	GAL	365	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	5,400	
AR701512	12" RCP, CLASS IV	LF	78	
AR701518	18" RCP, CLASS IV	LF	80	
AR752412	PRECAST REINFORCED CONC. FES 12"	EACH	8	
AR752418	PRECAST REINFORCED CONC. FES 18"	EACH	4	
AR752512	GRATING FOR CONC. FES 12"	EACH	8	
AR752518	GRATING FOR CONC. FES 18"	EACH	4	
AR800187	THRESHOLD LIGHT BAR	EACH	1	
AR901510	SEEDING	ACRE	2.0	
AR908510	MULCHING	ACRE	2.0	

REVISIONS


NUMBER	BY	DATE



**FREEPORT - ALBERTUS AIRPORT  
 FREEPORT, ILLINOIS**

ILLINOIS PROJECT, FEP-3132 / A.I.P. PROJECT, 3-17-0045-B16

**SUMMARY OF QUANTITIES**



DESIGN BY: CAL  
 DRAWN BY: JRO  
 CHECKED BY:  
 APPROVED BY:  
 DATE: 06/17/05  
 JOB No: 02294-08

SHEET 2 OF 34 SHEETS