

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

District 1  
Schedule of Overhead Sign Structure Repair & Replacement

Location No.:	1	State I.D. No.:	1S0991080L131.0				
County:	WILL	Route:	180	M.P.:	131.0	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	75.5					
Structural Steel Support for Overhead Sign Structure Span	EACH	2					
Remove and Re-erect Overhead Sign Structure-Truss	EACH	1					
Furnish and Install Saddle Shim Block	EACH	4					
Furnish and Install Internal Truss Damper	EACH	1					
<i>This work will be done during night time hours using District One "Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	5	State I.D. No.:	1S0991080R132.9				
County:	WILL	Route:	180	M.P.:	132.9	Direction:	EB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	79.00					
Remove and Re-erect Overhead Sign Structure-Span	EACH	1.00					
Rebuild Concrete Foundation for Overhead Sign Structure Span	EACH	2.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
Temporary Informational Signage	SQ FT	96.00					

Location No.:	9	State I.D. No.:					
County:		Route:		M.P.:		Direction:	
Description of Work	Unit	Quantity					
Intentionally Left Blank							
There is no Location # 9							

Location No.:	2	State I.D. No.:	1S0991080R133.2				
County:	Lake	Route:	180	M.P.:	133.2	Direction:	EB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	86.5					
Structural Steel Support for Overhead Sign Structure Span	EACH	2					
Remove and Re-erect Overhead Sign Structure-Truss	EACH	1					
Furnish and Install Saddle Shim Block	EACH	4					
Furnish and Install Internal Truss Damper	EACH	1					
<i>This work will be done during night time hours using District One "Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	6	State I.D. No.:	1C0991080L147.8				
County:	Will	Route:	180	M.P.:	147.8	Direction:	WB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	34.50					
Remove and Re-erect Overhead Sign Structure-Cantilever	EACH	1.00					
Rebuild Concrete Foundation for Overhead Sign Structure Cantil	EACH	1.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
Temporary Informational Signage	SQ FT	45.50					

Location No.:	10	State I.D. No.:	1C0991057R327.4				
County:	WILL	Route:	157	M.P.:	332.7	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	34.50					
Remove and Re-erect Overhead Sign Structure-Cantilever	EACH	1.00					
Repair Concrete Foundation for Overhead Sign Structure Cantile	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	1.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
<i>This work will be done during night time hours using District One "Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	3	State I.D. No.:	1S0991080L130.9				
County:	WILL	Route:	180	M.P.:	130.9	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	53					
Structural Steel Support for Overhead Sign Structure Span	EACH	2					
Remove and Re-erect Overhead Sign Structure-Truss	EACH	1					
Furnish and Install Saddle Shim Block	EACH	4					
Repair Concrete Foundation for Overhead Sign Structure Span	EACH	2					
Furnish and Install Internal Truss Damper	EACH	1					
Furnish and Install Safety Chain	EACH	2					
Furnish and Install Safety Metal Screen	EACH	1					
Replace Overhead Sign Structure Anchor Rods	EACH	4					
<i>This work will be done during night time hours using District One "Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	7	State I.D. No.:	1S0991080R131.8				
County:	Will	Route:	180	M.P.:	131.8	Direction:	eb
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	70.00					
Remove and Re-erect Overhead Sign Structure-Span	EACH	1.00					
Rebuild Concrete Foundation for Overhead Sign Structure Span	EACH	2.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
Temporary Informational Signage	SQ FT	63.75					

Location No.:	11	State I.D. No.:	1S0161057R341.4				
County:	COOK	Route:	157	M.P.:	340.4	Direction:	NB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	111.00					
Structural Steel Support for Overhead Sign Structure Span	EACH	2.00					
Remove and Re-erect Overhead Sign Structure-Truss	EACH	1.00					
Furnish and Install Saddle Shim Block	EACH	4.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
<i>All electrical work will be done by using our EMC</i>							
<i>This work will be done during night time hours using District One "Keeping the Expressway Open to Traffic" Special Provision</i>							

Location No.:	4	State I.D. No.:	1S0991080L133.7				
County:	WILL	Route:	180	M.P.:	133.7	Direction:	WB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	66.5					
Structural Steel Support for Overhead Sign Structure Span	EACH	2					
Remove and Re-erect Overhead Sign Structure-Truss	EACH	1					
Furnish and Install Saddle Shim Block	EACH	4					
Furnish and Install Internal Truss Damper	EACH	1					
<i>This work will be done during night time hours using District One "Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	8	State I.D. No.:	1S0991080L132.2				
County:	Will	Route:	180	M.P.:	132.2	Direction:	WB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	96.00					
Remove and Re-erect Overhead Sign Structure-Span	EACH	1.00					
Repair Concrete Foundation for Overhead Sign Structure (RT)	EACH	1.00					
Rebuild Concrete Foundation for Overhead Sign Structure (LT)	EACH	1.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
Temporary Informational Signage	SQ FT	71.25					

Location No.:	12	State I.D. No.:					
County:		Route:		M.P.:		Direction:	
Description of Work	Unit	Quantity					
Intentionally Left Blank							
There is no Location # 12							

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
		CHECKED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Various	D-1 OVD SIN STR REPL 12-02	VARIOUS	39	3
CONTRACT NO. 46175				
(ILLINOIS) FED. AID PROJECT				