

# SCHEDULE OF QUANTITIES

Location No.:	2-01	State I.D. No.:	2S081N000L000.0				
County:	ROCK ISLAND	Route:	7TH AVE	M.P.:	0	Direction:	WB
Description of Work	Unit	Quantity					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	86.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A (4'-6" X 5'-3")	FOOT	118.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	315.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
<i>The new foundations will be built in line with the existing footings.</i>							
<i>Center the new sign structure 25 feet east of the center of the existing structure.</i>							
SIGN # 46							

Location No.:	2-03	State I.D. No.:	2S081I080L003.6				
County:	ROCK ISLAND	Route:	I-80	M.P.:	3.8	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE AND RE-ERECT SPGR, TYPE A	FOOT	75.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	110.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	54.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	538.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 25 feet east of the existing structure.</i>							
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>							
SIGN # 100							

Location No.:	2-05	State I.D. No.:	2S098I088L036.4				
County:	WHITESIDE	Route:	I-88	M.P.:	36.4	Direction:	WB
Description of Work	Unit	Quantity					
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A (4'-6" X 5'-3")	FOOT	120.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	55.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	288.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 25 feet east of the existing structure.</i>							
SIGN # 131							

Location No.:	2-07	State I.D. No.:	2C101S251L009.6				
County:	WINNEBAGO	Route:	IL 251	M.P.:	9.6	Direction:	SB
Description of Work	Unit	Quantity					
OVERHEAD SIGN STRUCTURE-CANTILEVER TYPE II-C-A	FOOT	28.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	6.90					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	18.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	124.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 15 feet north of the existing structure.</i>							
<i>Build the new foundation with the same pavement offset as the old.</i>							
SIGN # 167							

Location No.:	2-02	State I.D. No.:	2S081I080R003.2				
County:	ROCK ISLAND	Route:	I-80	M.P.:	3.2	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE AND RE-ERECT SPGR, TYPE A	FOOT	75.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	110.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	48.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	478.00					
<i>Locate the new structure 25 feet west of the existing structure.</i>							
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>							
SIGN # 97							

Location No.:	2-04	State I.D. No.:	2S081I088R015.8				
County:	ROCK ISLAND	Route:	I-88	M.P.:	15.6	Direction:	EB
Description of Work	Unit	Quantity					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	84.00					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
REMOVE AND REINSTALL WALKWAY	FOOT	54.50					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	434.00					
<i>Locate the new structure 25 feet west of the existing structure.</i>							
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>							
SIGN # 102							

Location No.:	2-06	State I.D. No.:	2S081I280R010.8				
County:	ROCK ISLAND	Route:	I-280	M.P.:	10.8	Direction:	EB
Description of Work	Unit	Quantity					
STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	75.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	114.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	24.60					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	53.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	419.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 25 feet west of the existing structure.</i>							
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>							
SIGN # 135							

Location No.:	2-08	State I.D. No.:	2C101S251R009.6				
County:	WINNEBAGO	Route:	IL 251	M.P.:	9.6	Direction:	NB
Description of Work	Unit	Quantity					
OVERHEAD SIGN STRUCTURE-CANTILEVER TYPE II-C-A	FOOT	30.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	8.60					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	19.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	75.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 15 feet south of the existing structure.</i>							
<i>Build the new foundation with the same pavement offset as the old.</i>							
SIGN # 168							