

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE									
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED/ST	FED/ST	FED/ST/CITY	FED/ST	CITY	FED/ST	PRE-EMPTION EQUIPMENT	LAND-SCAPING	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED/ST	FED/ST	FED/ST/CITY	FED/ST	CITY	FED/ST	PRE-EMPTION EQUIPMENT	LAND-SCAPING	
				0004	0021	0021	0021	0021	0031							0004	0021	0021	0021	0021	0031			
				(80/20)	(80/20)	(80/10/10)	(80/20)			(100% CITY)	(80/20)													
* M8860100	DETECTOR LOOP, TYPE I	METER	261																					
* M8731850	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR NO. 6 IC	METER	323																					
	DRILLING AND SETTING SOLDIER PILES	CU-M	90								90													
* MX873030	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	METER	82																					
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	10360	10360																				
28000510	INLET FILTERS	EACH	37								37													
MX030428	STORM SEWER, WATER MAIN TYPE 3 450 mm	METER	24	24																				
* X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	1																					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	2	2																				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	10	10																				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	15	15																				
X4023000	TEMPORARY ACCESS (ROAD)	EACH	12	12																				
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1																					
* 88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	6																					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																				
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	37	37																				
Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	10								10													
* MX816074	UNIT DUCT, 600V, 3-1/C #4 AND 1/C #6 GROUND, (XLP-TYPE RHW) 30 MM DIA., SCHEDULE 40 POLYETHYLENE	METER	440								440													

* Specialty Items

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES IL. 50 AT COURT STREET
NAME	DATE	

Rev. 7-26-11