

INDEX OF SHEETS

LIST OF STATE STANDARDS

RTE.	SECTION	COUNTY	SHEETS NO.
840	143N	WILL	121 2
STA.		TO STA.	
CONTRACT NO. - 60445			

PAGE NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STATE STANDARDS, PLAN NOTES
3-6	SUMMARY OF QUANTITIES
7-12	TYPICAL CROSS SECTIONS
13-14	ALIGNMENT TIES
15-30	SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL
31-32	DETOUR PLANS
33-36	EXISTING AND PROPOSED ROADWAY PLAN
37-38	EXISTING AND PROPOSED ROADWAY PROFILE
39-40	SUE INVESTIGATION OF UNDERGROUND UTILITIES
41-44	EXISTING AND PROPOSED DRAINAGE & UTILITIES PLAN
45-46	EXISTING AND PROPOSED DRAINAGE PROFILE
47-48	PROPOSED DRAINAGE STRUCTURE AND PIPE TABLES
49-53	RIGHT OF WAY PLATS
54-56	PROPOSED PAVEMENT ELEVATION PLAN
57-58	PAVEMENT MARKING AND LANDSCAPING DETAILS
59-60	EROSION AND SEDIMENT CONTROL PLAN
61-72	TRAFFIC SIGNALS
73-80	LIGHTING
81-90	RETAINING WALLS DETAILS AND CROSS SECTIONS- DELETED
91-107	CROSS SECTIONS
108	DRIVEWAY DETAILS DISTANCE BETWEEN R.O.W. AND FACE OF CURB < 4.5 M (15 FT.)
109	DETAIL OF STORM SEWER CONNECTION TO EXISTING SEWER
110	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING
111	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT
112	CURB OR CURB & GUTTER REMOVAL & REPLACEMENT
113	BUTT JOINT AND HMA TAPER DETAIL
114	FIRE HYDRANT TO BE MOVED
115	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
116	TYPICAL APPLICATION RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
117	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
118	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
119	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
120	ARTERIAL INFORMATION SIGNING
121	DIST. 1 DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING

STANDARD NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
420001-07	PAVEMENT JOINTS
424001-05	SIDEWALK RAMPS ACCESSIBLE TO THE DISABLED
442201-03	CLASS C & D PATCHES
482001-02	HMA SHOULDER DETAILS - RESURFACING OR WIDENING OF RESURFACING PROJECTS
482011-03	SHOULDER STRIPS / SHOULDERS WITH RESURFACING OR WIDENING & RESURFACING PROJECTS
602001-02	CATCH BASIN, TYPE A
602301-03	INLET, TYPE A
602401-03	MANHOLE, TYPE A
602701-02	CAST IRON STEPS
604001-03	FRAME AND LIDS, TYPE 1
604036-02	GRATE, TYPE 8
604091-02	FRAME AND GRATE, TYPE 24
606001-04	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER
606006-02	OUTLET FOR CONCRETE CURB AND GUTTER, TYPE B-15.60 (6.24)
701201-04	LANE CLOSURE, 2L, 2W, DAY ONLY ON-RD TO 600 MM (24") OFF-RD FOR SPEEDS > 45 MPH
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS FOR SPEEDS > 45 MPH
701306-03	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS - DAY ONLY FOR SPEEDS > 45 MPH
701326-04	LANE CLOSURE 2L, 2W, PAVEMENT WIDENING FOR SPEEDS > 45 MPH
701501-06	URBAN LANE CLOSURE 2L, 2W UNDIVIDED
701606-07	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-07	URBAN LANE CLOSURE MULTI LANE INTERSECTION
701901-01	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
780001-02	TYPICAL PAVEMENT MARKINGS
877001-04	STEEL MAST ARM ASSEMBLY AND POLE
878001-06	CONCRETE FOUNDATION DETAILS
880006-01	TRAFFIC SIGNAL MOUNTING DETAILS
886001-01	DETECTOR LOOP INSTALLATIONS
857001-01	STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
805001-01	ELECTRICAL SERVICE INSTALLATION DETAILS

PLAN NOTES (CONTINUED)

UNLESS OTHER CONDITIONS WARRANT EXTENDED LANE CLOSURE AS DETERMINED AND APPROVED IN WRITING BY THE ENGINEER OR AS PROVIDED FOR IN THE CONTRACT SPECIFICATIONS, OVERNIGHT CLOSURES SHALL NOT BE ALLOWED FOR REHABILITATION PROJECTS INVOLVING DAYTIME MILLING AND RESURFACING OPERATIONS AND CLASS D PATCHING.

IT IS THE GENERAL CONTRACTORS RESPONSIBILITY TO HIRE AN ENVIRONMENTAL FIRM TO MONITOR FOR SOIL CONTAMINATION AND WORKER PROTECTION AT SEVERAL LOCATIONS - SEE SPECIAL PROVISIONS.

PRIOR TO EMBANKMENT PLACEMENT, ALL VEGETATION, LOOSE MATERIAL, AND UNSTABLE MATERIAL SHOULD BE REMOVED TO DEPTH ENCOUNTERED AND REPLACED WITH SUITABLE EMBANKMENT MATERIAL. ANY EMBANKMENT WIDENING ON EXISTING SLOPES SHOULD BE BENCHED IN ACCORDANCE WITH ARTICLE 205.04 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

IT IS THE CONTRACTORS RESPONSIBILITY TO PROVIDE A FIELD LABORATORY FOR USE FOR ANY ON SITE TESTING BY THE ENVIRONMENTAL FIRM. NO TESTING OF ANY KIND, CONTAMINATED OR NON CONTAMINATED FLUID OR SOLID SHALL BE PERMITTED IN THE ENGINEER'S FIELD OFFICE.

ALL PLANT MATERIAL SHALL BE MARKED IN THE FIELD. CALL STEVEN LIPKE (847) 705-4173, 72 HOURS PRIOR TO LANDSCAPING WORK.

THE RESIDENT ENGINEER SHALL CONTACT LAWRENCE HILL, AREA TRAFFIC FIELD ENGINEER AT (815) 488-6475 A MINIMUM OF 2 WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

3 METER (10 FEET) TRANSITIONS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURBS & GUTTERS AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL OVERHEAD, SURFACE AND UNDERGROUND UTILITIES WITHIN THE PROJECT LIMITS WHETHER OR NOT THE UTILITIES ARE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT HIS OWN EXPENSE.

EXISTING SEWER LOCATIONS SHOWN ARE FROM AVAILABLE INFORMATION. CONTRACTOR SHALL FIELD VERIFY THEIR LOCATIONS.

WHEN CONSTRUCTING SIDEWALK RAMPS FOR THE HANDICAPPED, STATE STANDARD 424001 USE TYPE B RAMPS UNLESS OTHERWISE SPECIFIED.

ALL PROPOSED DRIVEWAYS SHALL BE HMA UNLESS OTHERWISE SPECIFIED AS PORTLAND CEMENT CONCRETE ON THE PLAN SHEETS.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE MARKINGS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKINGS OUTSIDE OF THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE DEPARTMENT.

PAVEMENT MARKING TAPE, TYPE III SHALL BE USED FOR SHORT TERM PAVEMENT MARKINGS ON ALL FINAL SURFACES. THE COST OF THE PAVEMENT MARKING TAPE, TYPE III AND ITS REMOVAL SHALL BE INCLUDED IN THE COST OF THE SHORT TERM PAVEMENT MARKING.

PAVEMENT MARKING TAPE, TYPE III SHALL BE USED FOR SHORT TERM PAVEMENT MARKINGS ON ALL FINAL SURFACES. THE COST OF THE PAVEMENT MARKING TAPE, TYPE III AND ITS REMOVAL SHALL BE INCLUDED IN THE COST OF THE SHORT TERM PAVEMENT MARKING.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

PLAN NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE VILLAGE OF MONEE IN WILL CO.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED FOR STABILIZATION. ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SANDBAGS PER BARRICADE.

WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 40 MM (1 1/2 INCHES) WHERE THE SPEED LIMIT IS 80 KM/H (45 MPH) OR LESS AND 25 MM (1 INCH) WHERE THE SPEED LIMIT IS GREATER THAN 80 KM/H (45 MPH). WITH WRITTEN APPROVAL FROM THE ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 75 MM (3 INCHES) MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM 1:3 (V:H).

BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND HMA TAPER DETAILS" SHEET INCLUDED IN THE PLANS, UNLESS OTHERWISE SPECIFIED.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAP ROUTE 840 (IL ROUTE 50) COURT STREET INDEX OF SHEETS LIST OF STATE STANDARDS PLAN NOTES
NAME	DATE	
		SCALE DATE 5/12/2011 DRAWN BY CHECKED BY