



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = lseye	DESIGNED -	REVISED - R. MIRS 09-15-97
ci:\pwork\pwork\lseye\d0190226\01stStd.dgn		DRAWN -	REVISED - R. MIRS 12-11-97
PLOT SCALE = 50.0000 "/td> <td></td> <td>CHECKED -</td> <td>REVISED - T. RAMMACHER 02-02-99</td>		CHECKED -	REVISED - T. RAMMACHER 02-02-99
PLOT DATE = 1/10/2011		DATE -	REVISED - C. JUCIUS 01-31-07

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ARTERIAL ROAD INFORMATION SIGN	
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS
STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	143 N	WILL	121	120
TC-22			CONTRACT NO. 60445	
<small>FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT</small>				