

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE				
				0004		0021	0011	0021
				KEDZIE AVE.	I-57	SIGNING	SNO16-1196	LIGHTING
58700300	CONCRETE SEALER	SQ FT	2170				2170	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	153				153	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2	2				
60107600	PIPE UNDERDRAINS 4"	FOOT	177	177				
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	3	3				
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2				
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60224039	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1				
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	2	2				
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	3	3				
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	14	14				
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	11	11				
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	19	19				
60500040	REMOVING MANHOLES	EACH	4	4				
60500060	REMOVING INLETS	EACH	8	8				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1808.0	1808.0				
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	1816.0	1816.0				
60624700	CORRUGATED MEDIAN (SPECIAL)	SO FT	14438	14438				
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	2137.5	2137.5				
63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FOOT 6 INCH SPAN	FOOT	162.5	162.5				
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2				
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2				
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2				
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2				
63200310	GUARDRAIL REMOVAL	FOOT	2408	2408				
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	200.0		200.0			
63700805	CONCRETE BARRIER TRANSITION	FOOT	30		30			
64200105	SHOULDER RUMBLE STRIPS	FOOT	235		235			
66400305	CHAIN LINK FENCE, 6'	FOOT	257	257				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12				
67100100	MOBILIZATION	L SUM	1	1				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	10999	10218	781			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2362.5	1537.5	825.0			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4767.5	3187.5	1580.0			
72000100	SIGN PANEL - TYPE 1	SO FT	100			100		
72000300	SIGN PANEL - TYPE 3	SO FT	653			653		
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	17			17		

• SPECIALTY ITEM

TYLIN INTERNATIONAL	USER NAME = #USER#	DESIGNED - EMK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	KEDZIE AVENUE PROJECT SUMMARY OF QUANTITIES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = #SCALE#	DRAWN - EMK	REVISED -		57	1313.1B-1	COOK	162	7			
	PLOT DATE = 5/4/2011	CHECKED - SES	REVISED -		SCALE: NTS SHEET NO. 3 OF 5 SHEETS STA. TO STA.			CONTRACT NO. 60K14				
DATE - 5/5/2011				REVISED -		FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT				