

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE				
				0004		0021	0011	0021
				KEDZIE AVE.	I-57	SIGNING	SNO16-1196	LIGHTING
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	2			2		
* 72700100	STRUCTURAL STEEL SIGN SUPPORT-BREAKAWAY	POUND	5310			5310		
* 72900200	METAL POST - TYPE B	FOOT	345			345		
* 73000100	WOOD SIGN SUPPORT	FOOT	54			54		
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	14			14		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	153	153				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13292	13292				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	704	704				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3002	3002				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	134	134				
* 78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	480		480			
* 78008220	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 5"	FOOT	240	240				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	347	347				
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	32	32				
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	578	382	196			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	32				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2				
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	7465	7465				
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	347	347				
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	706					706
* 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	40					40
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	8					8
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	9					9
* 81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	2					2
* 81603050	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYTHEYLENE	FOOT	255					255
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2640					2640
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	235					235
* 82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8					8
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	12					12
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	236	236				
XX006172	ROUTING AND SEALING CRACKS	FOOT	4347	4347				
X0321750	REMOVE TEMPORARY CONCRETE BARRIER, STATE OWNED	FOOT	380		380			
X0326382	CONCRETE BARRIER BASE (SPECIAL)	FOOT	50		50			
X2011000	TEMPORARY FENCE (SPECIAL)	FOOT	490	490				
X2020502	BRACED EXCAVATION	CU YD	351				351	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	331				331	
X2800510	INLET FILTER CLEANING	EACH	205	205				
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	1501	1135	366			
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	1374	1374				

TYLIN INTERNATIONAL

USER NAME = #USER#
 PLOT SCALE = #SCALE#
 PLOT DATE = 5/4/2011

DESIGNED - EMK
 DRAWN - EMK
 CHECKED - SES
 DATE - 5/5/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**KEDZIE AVENUE PROJECT
 SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 4 OF 5 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	1313.1B-1	COOK	162	8
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60K14	

* SPECIALTY ITEM

Rev.