


SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	PED SIGNAL	SIDEWALK	TREE
				HSIP 90% FED 10% STATE 0005	50% STATE 25% COUNTY 25% CITY 0021	80% STATE 20% CITY 0021	REPLACEMENT 100% CITY 0031
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	27	-	-	-	27
20200100	EARTH EXCAVATION	CU YD	1010	1010	-	-	-
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	490	490	-	-	-
20400800	FURNISHED EXCAVATION	CU YD	25	25	-	-	-
20800150	TRENCH BACKFILL	CU YD	231.6	231.6	-	-	-
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1065	1065	-	-	-
* 25200110	SODDING, SALT TOLERANT	SQ YD	1065	1065	-	-	-
28000400	PERIMETER EROSION BARRIER	FOOT	500	500	-	-	-
28000510	INLET FILTERS	EACH	30	30	-	-	-
<del>35501327</del>	<del>HOT-MIX ASPHALT BASE COURSE, 10 3/4"</del>	<del>SQ YD</del>	<del>919</del>	<del>919</del>	<del>-</del>	<del>-</del>	<del>-</del>
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.79	0.79	-	-	-
40600300	AGGREGATE (PRIME COAT)	TON	3.94	3.94	-	-	-
<del>40603090</del>	<del>HOT MIX ASPHALT BINDER COURSE, IL 19.0, N90</del>	<del>TON</del>	<del>544</del>	<del>544</del>	<del>-</del>	<del>-</del>	<del>-</del>
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	221	221	-	-	-
42001300	PROTECTIVE COAT	SQ YD	3435	3435	-	-	-
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2493	-	-	2493	-
42400800	DETECTABLE WARNINGS	SQ FT	48	-	-	48	-
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1068	1068	-	-	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1205	1205	-	-	-
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1850	1850	-	-	-
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	50	50	-	-	-
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	194	194	-	-	-
44003100	MEDIAN REMOVAL	SQ FT	9570	9570	-	-	-
44000600	SIDEWALK REMOVAL	SQ FT	195	-	-	195	-
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	21	21	-	-	-
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	47	47	-	-	-
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	252	252	-	-	-
550A4500	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	146	146	-	-	-
55100900	STORM SEWER REMOVAL 18"	FOOT	140	140	-	-	-
55101200	STORM SEWER REMOVAL 24"	FOOT	249	249	-	-	-
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	-	-	-
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	-	-	-
60200205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	-	-	-

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	PED SIGNAL	SIDEWALK	TREE
				HSIP 90% FED 10% STATE 0005	50% STATE 25% COUNTY 25% CITY 0021	80% STATE 20% CITY 0021	REPLACEMENT 100% CITY 0031
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	4	4	-	-	-
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2	2	-	-	-
60211800	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	-	-	-
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	-	-	-
60236600	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	EACH	2	2	-	-	-
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	-	-	-
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2	-	-	-
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2	-	-	-
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	94	94	-	-	-
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	386	386	-	-	-
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	321	321	-	-	-
60624600	CORRUGATED MEDIAN	SQ FT	2910	2910	-	-	-
63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	166	166	-	-	-
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	5	5	-	-	-
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	-	-	-
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	-	-	-
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	-	-	-
67100100	MOBILIZATION	L SUM	1	1	-	-	-
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	-	-	-
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	530	530	-	-	-
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36.4	36.4	-	-	-
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6630	6630	-	-	-
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	350	350	-	-	-
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	1000	1000	-	-	-
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	88	88	-	-	-
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	218.4	218.4	-	-	-
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2125	2125	-	-	-
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	816	816	-	-	-
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	43	43	-	-	-
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	83	83	-	-	-
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	2065	2065	-	-	-
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	83	83	-	-	-

\* SPECIALTY ITEM

FILE NAME : P:\2009\ME0908\VerVer\_Phil\CADD\W022\_US34\Shva\03-S00\ht-ht-US34.dgn  
 PLOT SCALE : 1:1000  
 USER NAME : Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.705.0110 voice, 630.839.2566 fax  
 www.mps-ill.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED -	CJD	REVISED -	
DRAWN -	CJD	REVISED -	
CHECKED -	TVN	REVISED -	
DATE -	6/1/2011	REVISED -	

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**US ROUTE 34  
 AT NORTH AURORA ROAD /RAYMOND DRIVE**

**SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652X-N-3	DUPAGE	34	3
CONTRACT NO. 60L22			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

Rev. 7-19-11