

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	25	25					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6020	6020				
25200110	SODDING, SALT TOLERANT	SO YD	25	25					*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	320	320				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8					*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	45	45				
40600300	AGGREGATE (PRIME COAT)	TON	40	40					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	39	39				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	115	115				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	103	103				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	111	111					*88600600	DETECTOR LOOP REPLACEMENT	FOOT	66	66				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	104	104					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	332	332				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	827	827					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	15	15				
42001300	PROTECTIVE COAT	SO YD	34	34					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	150	150				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	1812	1812					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	8028	8028					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	52	52				
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SO YD	529	529													
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	170	170													
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	110	110													
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	180	180													
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2570	2570													
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	37	37													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6020	6020													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	320	320													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	45	45													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	40	40													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	860	860													
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	37	37													