SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	34	34					
25200110	SODDING, SALT TOLERANT	SQ YD	34	34					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	14					
40600300	AGGREGATE (PRIME COAT)	TON	70	70					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	27	27					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	181	181					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1463	1463					
42001300	PROTECTIVE COAT	SQ YD	45	45					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	17410	17410					
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	450	450					
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	110	110					
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	540	540					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	190	190					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	6	6					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2838	2838					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	218	218					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16362	16362					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	764	764					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	69	69					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	119	119					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	946	946					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	218	218					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16362	16362					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	764	764					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	69	69					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	119	119					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	164	164					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	148	148					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1518	1518					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	48	48					
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	719	719					
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

* SPECIALTY ITEMS

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
c:\pw_work\pwidot\bastlnml\d0246754\D10961I-sht-plan.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 5/17/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WOLF ROAD (FRANKLIN ST. TO GRAND AVE.)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2690	2527 RS-2	COOK	22	3
		CONTRACT NO. 60M29		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT